

DEC 02 1993

RC 1135

LI26985 PA 926

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE (County)

Located In: Corner Code #

- 1. Public Land Survey T 2S R 9E G-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11/24/93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Grid table with columns A-K and rows 2-13. A black dot is located at the intersection of column G and row 3.

I, P.P. Palczynski in a field survey on 4 October 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NANKIN TOWNSHIP

G.L.O.- (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES.

WITNESSES LISTED: WO 9 S27W 12 (7.9') (GONE) & DO." 6 N67E 6 (4.0') (GONE)

W.P.A.- (1930'S) STONE. WITNESSES SHOWN: 10" ASH NE 92.20' (GONE)
8" ELM NE 61.50' (GONE)
20" CULVERT SE 71.05' (GONE)
20" OAK SE 248.00' (NA) ED. POLE NW 54.40' (GONE)

C.S.#1939 L.23982 P.825(10-26-88). NO SUBSEQUENT L.C.R.C. AT WAYNE CO. REG. DEEDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN CONC. MON. IN MONUMENT BOX AT WARREN / FARMINGTON ROADS.

MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:

G-3/G-2: W.P.A. = 2656.24' MEAS. = 2655.91'
C.S. #1939: 2655.75' (10-26-88)
G-3/F-3: W.P.A. = 2639.08' MEAS. = 2639.28'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3: SECTION CORNER 3,4,9 &10, T2S, R9E, FOUND 3/4" IRON PIPE/CONC. MON. IN MON. BOX. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

FOUND CONCRETE MONUMENT. (BROKEN). NORTH 59.91'
SET NAIL/WCR TAG IN W FACE UTILITY POLE. N10°E 49.38'
SET NAIL/WCR TAG IN SE FACE UTILITY POLE. N45°E 88.73'
SET NAIL/WCR TAG IN NE FACE UTILITY POLE. S45°E 74.56'
SET NAIL/WCR TAG IN WEST FACE UTILITY POLE. S10°E 52.47'
SET CUT "X" IN SW BOLT OF LIGHT POLE BASE. N50°W 66.92'

Signed by [Signature] Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

Handwritten initials: 2R 11K D