

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

WAYNE (County) Located In: Corner Code #

1. Public Land Survey T 2 S R 9 E G-9  
T R CITY OF WESTLAND  
T R NANKIN TOWNSHIP  
T R

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-14-95

WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number 95270182

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1816 G.L.O. - SET POST B.O. 12" S70°E 26 LKS.  
JOSEPH FLETCHER Do. 10" S11°E 3 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

\$ 10.00 DEED  
18 DEC 95 3:00 P.M. RECEIPT# 75B  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
\$ 4.00 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" STEEL BAR IN CONCRETE MONUMENT, OFFSET FROM CENTER OF MONUMENT BOX, AT CENTERLINE OF PALMER ROAD IN ASPHALT PAVEMENT.  
CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".  
MEASURED:  
G-9 / F-9 = 2623.31' (WPA = 2623.21')  
G-9 / H-9 = 2632.13' (WPA = 2631.24')

MEASURED:  
F-9/G-9/H-9 = 179°27'07"  
(WPA = 179°28'40")  
H-9/G-9/F-9 = 180°32'53"  
(WPA = 179°10'50")  
(WPA DID NOT = 360° +/-)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
G-9, T2S, R9E  
FOUND 1/2" STEEL BAR IN CONCRETE MONUMENT, OFFSET FROM CENTER OF MON BOX, AT CENTERLINE OF PALMER ROAD IN ASPHALT PAVEMENT, MONUMENT WAS UNDER PAVEMENT, NOT CENTERED IN MON. BOX. RESET MON BOX OVER FCM & SET WAYNE COUNTY REMON. BRASS MARKER AND CAP "PPP PS 30096" ON MON.  
CENTERLINE OF 2" DIAMETER STEEL FENCE POST  
SET NAIL/WCR TAG IN SOUTHEAST FACE 48" ELM  
CENTERLINE OF FIRE HYDRANT STEM  
SET NAIL/WCR TAG IN SOUTHWEST FACE OF 15" MAPLE  
SET NAIL/WCR TAG IN NORTHWEST FACE OF 10" APPLE TREE  
SET NAIL/WCR TAG IN SOUTHWEST FACE OF 13" ELM  
NORTH 30.29'  
N55°E 86.45'  
S74°E 133.69'  
S54°E 113.76'  
S31°W 59.27'  
N74°W 109.93'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 15 DEC 95

**1995 WAYNE COUNTY REMONUMENTATION PROGRAM**

Continuation of Section "A"

History compiled by:  
Peter P. Palczynski, P.S. # 30096  
AMBIT LAND SURVEYING & S, INC.

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST  
G-9 (SECTION CORNER 21,22,27 & 28)

| DATE | COMPANY SURVEYOR JOB # | P.S. # | LOCATION OF SURVEY | MONUMENT DESCRIPTION | WITNESSES | BEARING & DISTANCE | ID # | COMMENT |
|------|------------------------|--------|--------------------|----------------------|-----------|--------------------|------|---------|
|------|------------------------|--------|--------------------|----------------------|-----------|--------------------|------|---------|

|      |                        |  |          |  |                      |                               |  |                      |
|------|------------------------|--|----------|--|----------------------|-------------------------------|--|----------------------|
| 1816 | G.L.O. JOSEPH FLETCHER |  | SET POST |  | B.O. 12"<br>D.O. 10" | S70°E 26 LKS.<br>S11°E 3 LKS. |  | NOTES = 40.00 STAINS |
|------|------------------------|--|----------|--|----------------------|-------------------------------|--|----------------------|

|        |        |  |                    |  |  |   |                  |  |
|--------|--------|--|--------------------|--|--|---|------------------|--|
| 1930'S | W.P.A. |  | STONE (NW-27 #111) | TEL. POLE<br>EDISON POLE<br>18" MAPLE<br>18" MAPLE |  | NE 29.78'<br>SE 64.25'<br>SOUTH 25.20'<br>NW 89.47' | 1<br>2<br>3<br>4 | GONE<br>GONE<br>GONE<br>GONE<br>W.P.A. RECORD:<br>G-9 / G-8 = 2610.42' & 2610.69'<br>G-9 / H-9 = 2631.24' & 2630.06'<br>G-9 / G-10 = 2637.21' & 2636.99'<br>G-9 / F-9 = 2623.21' & 2622.62'<br>F-9 / G-9 / G-8 = 89°15'20"<br>G-8 / G-9 / H-9 = 90°13'30"<br>H-9 / G-9 / G-10 = 89°5'00"<br>G-10 / G-9 / F-9 = 89°19'50" |
|--------|--------|--|--------------------|--|--|---|------------------|--|

|      |                              |  |                               |                                |  |                                     |             |                      |
|------|------------------------------|--|-------------------------------|--------------------------------|--|-------------------------------------|-------------|----------------------|
| 1985 | WAYNE COUNTY ROAD COMMISSION |  | SECTION CORNER WITNESS RECORD | 1/2" IRON PIPE IN MONUMENT BOX |  | NE 85.45'<br>SW 32.62'<br>SW 59.33' | 5<br>6<br>7 | GONE<br>GONE<br>GONE |
|------|------------------------------|--|-------------------------------|--------------------------------|--|-------------------------------------|-------------|----------------------|

|      |   |        |                               |                          |                    |            |  |              |
|------|---|--------|-------------------------------|--------------------------|--------------------|------------|--|--------------|
| 1988 | BOSS ENGINEERING GARY R. BOSS, RLS & PE JOB # 88045 | #17022 | SECTION CORNER WITNESS RECORD | CS #1936 L.23865, P. 279 | NE. 1/4 SECTION 28 | NOT STATED |  | NO WITNESSES |
|------|---|--------|-------------------------------|--------------------------|--------------------|------------|--|--------------|

FILED DO NOT MAIL