

**SURVEY &
REMONUMENTATION**

RC 1464

LI27795PA299

APR 25 1995

\$ 13.00 MISCELLANEOUS RECORDING
22 DEC 94 12:03 P.M. RECEIPT# 358

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E G-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



Compliance with
ACT 345, P.A. 1990
APPROVED ON: 11-21-94 *JPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, P.P. Palczynski, in a field survey on 7 November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL G.L.O. SURVEYOR: FLETCHER - MAY 27, 1817.

NANKIN TOWNSHIP

DESCRIPTION OF POST SET FOR CORNER MONUMENT NOT STATED IN FIELD NOTES.

WITNESSES LISTED: W.O. 20 N9E 36 (23.8') (GONE) & MAPLE 10 N23W 36 (23.8) (GONE)

G.L.O. NOTES - T3S, R9E: "FELL 11 (7.26') EAST OF POST COR. SEC. 33, 34 T2S, R9E"

W.P.A.-(1930'S) SW-34 IRON. WITNESSES SHOWN: 12" ELM NE 57.46' (GONE)

IRON EAST 7.27'; (MEAS=7.33') TEL POLE SE 63.86' (GONE)

ED POLE NW 55.90' (GONE)

NO SUBSEQUENT RC OR CS FORMS AT WAYNE COUNTY REGISTER OF DEEDS THIS DATE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE IN STEEL ENCASED CONC MON/MON BOX IN VAN BORN ROAD. (ASP PVT)

MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:

G-13/F-13 W.P.A. = 2622.86' MEAS. = 2623.07'

G-13/H-13 W.P.A. = 2643.33' MEAS. = 2643.40'

F-13/G-13/H-13 W.P.A. = 179° 49' 30" MEAS. = 179° 49' 54"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13:SECTION CORNER 33&34 T2S R9E, FOUND 1" IRON PIPE IN CONC MON/MON BOX. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

SET NAIL/WCR TAG IN WEST FACE OF UTILITY POLE N13°E 33.51'

FOUND 1" IRON PIPE IN CONC MON/MON BOX EAST 7.33'

SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE. S45°E 63.01'

SET NAIL/WCR TAG IN WEST FACE OF 14" BEECH S10°W 49.19'

SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE. S63°W 97.74'

SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE. N56°W 56.86'

*2R
11-D-MISC*

Signed by *PP*

Date 22 DEC 94

Surveyor's Michigan License No. 30096