

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE Located In: Corner Code #
(County)

1. Public Land Survey T 2S R 9E H-13
T _____ R _____ CITY OF WAYNE
T _____ R _____ NANKIN TOWNSHIP
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-11-97 *DPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PETER P. PALCZYNSKI in a field survey on 1 DECEMBER, 19 97,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1816 G.L.O. - SET POST POPLAR 6" N70°E 45 LKS.
JOSEPH FLETCHER Do. 9" N34°E 19 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

\$4.00 REMONUMENTATION
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #42946

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

SET CONCRETE MONUMENT AND MONUMENT BOX IN CENTERLINE OF VAN BORN ROAD E OF VENOY IN 51' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS; 13.69' EAST OF RAILROAD SPIKE AT H-1, T3S, R9E. SET GREY "WAYNE COUNTY REMONUMENTATION" CAP ON CONCRETE MONUMENT IN MON BOX.

MEASURED:
G-13/H-13/1-13 = 179°59'06" (WPA=179°59'10")
I-13/H-13/G-13 = 180°00'54" (WPA=180°00'50")

H-13 IN T2S, R9E, IS NOT THE SAME CORNER AS H-1, T3S, R9E.

CORNER POSITION VERIFIED USING 8 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
H-13 / I-13 = 2625.71' (WPA = 2625.43')
H-13 / G-13 = 2643.33' (WPA = 2643.43')

SURVEY &
REMONUMENTATION
MAR 17 1998
SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13, T2S, R9E
SET CONCRETE MONUMENT AND MONUMENT BOX IN CENTERLINE OF VAN BORN ROAD E OF VENOY IN 51' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS, 13.69' EAST OF RAILROAD SPIKE AT H-1, T3S, R9E. SET GREY "WAYNE COUNTY REMONUMENTATION" CAP ON CONCRETE MONUMENT IN MON BOX.

CENTERLINE OF FIRE HYDRANT STEM (6) (R=63.55') N41°E 63.59'
SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE (7) N47°E 50.18'
FOUND P.K. NAIL IN NORTHWEST FACE OF SAME U POLE (7) (R=50.13') N47°E 50.13'
SET NAIL/WCR TAG IN NORTHEAST FACE OF 8' ELM S69°E 169.05'
FOUND STEEL BAR WITH CAP "19836 / 18663" SOUTH 59.92'
SET NAIL/WCR TAG IN SOUTHEAST FACE OF 24" OAK (8) (R=134.10') S69°W 134.10'
FOUND RR SPIKE AT H-1, T3S, R9E (4) (R=13.81') WEST 13.69'
SET NAIL/WCR TAG IN SW FACE OF UTILITY POLE N72°W 116.33'
BACK OF CONCRETE CURB NORTH 24.85'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *PP* Date 11 DEC 97

Surveyor's Michigan License No. 30096
2S9EH-13.DOC

DPJ

1997 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

History compiled by:
Peter P. Palczynski, P.S. # 30096
AMBIT LAND SURVEYORS, INC.

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST
H-13 (SOUTH 1/4 CORNER SECTION 34)

DATE	COMPANY SURVEYOR JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER			SET POST FOR H-13 T.2S., R.9E., NANKIN.	POPLAR 6" Do. 9"	N70°E 45 LKS. N34°E 19 LKS.		NOTES = 40.00 CHAINS
1930'S	W.P.A.			CROSS (S-34 #162 FOR NANKIN TOWNSHIP T2S, R9E)	TWIN OAK 4" ELM 4" ELM CROSS SET FOR H-1, T3S, R9E	NE 53.85' SE 51.45' SW 71.85' WEST 13.81'	1 2 3 4	GONE GONE GONE M = 13.69' TO RR SPIKE
31 MAY 94	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON, P.S. JOB # 93-8-1	P.S. #19836	PART OF THE NORTH 1/2 OF SECTIONS 3 & 4, T.3S., R.9E., CITY OF ROMULUS, WAYNE CO., MICHIGAN	SET R.R. SPIKE	PK NAIL S/S DE POLE TOP BOLT HYDRANT PK NAIL NW/S DE POLE PK NAIL N/S 18" ELM RR SPIKE (N 1/4 COR SEC 3) H-13/I-13 H-13/G-13 G-13/H-13/I-13	N75°W 102.94' N40°E 63.55' N45°E 50.15' S70°W 134.10' WEST 13.81' 2625.47' 2643.36' 179°59'10"	5 6 7 8 4 9 10 11	NEW POLE M = 63.59' M = 50.13' M = 134.10' M = 13.69' M = 2625.71' M = 2643.33' M = 179°59'06"

W.P.A. RECORD:

H-13 / I-13 = 2625.43'
H-13 / G-13 = 2643.43'
G-13/ H-13 / I-13 = 179°59'10"
I-13/ H-13 / G-13 = 180°00'50"

SURVEY & REMONUMENTATION

MAR 17 1998

SECTION