

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

LIBER 28469 PAGE 646

WAYNE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2 S R 9 E I-3
T R CITY OF WESTLAND
T R NANKIN TOWNSHIP
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-14-95
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

95270179

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST W.O. 16" S65°W 27 LKS.
JOSEPH FLETCHER BEECH 16" S32°E 53 LKS.

\$ 4.00 REMONUMENTATION
\$ 10.00 DEED
18 DEC 95 3:01 P.M. RECEIPT# 75B
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" STEEL BAR IN GRASS ISLAND AT MERRIMAN RD. & WARREN RD. SET CONCRETE MONUMENT IN MONUMENT BOX WITH GRAY WCR CAP. MEASURED: 1-3/1-4 = 90°15'02"

CORNER POSITION VERIFIED USING 3 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
1-3 / 1-4 = 2632.35'
1-3 / H-3 = 2622.27'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3, T2S, R9E	FD PK NAIL/WCRC REF PT BRASS TAG IN SW FACE OF UTILITY POLE(9)	N42°E	41.07'
FOUND 5/8" STEEL BAR IN GRASS ISLAND AT MERRIMAN RD. & WARREN RD. SET CONCRETE MONUMENT IN MONUMENT BOX WITH ALUMINUM WCR CAP.	FOUND CHISELED "X" T/CURB AT EXP JOINT IN MERRIMAN ROAD (10)	S75°E	74.66'
	SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE	S48°E	164.05'
	FOUND CHISELED "X" T/CURB AT EXP JOINT IN MERRIMAN ROAD (11)	S38°E	81.85'
	SET CUT "X" IN NORTHEAST BOLT OF LIGHT POLE	S13°W	120.15'
	SET NAIL/WCR TAG IN SOUTH FACE OF UTILITY POLE	N79°W	179.05'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by

[Signature]

Date 15 DEC 95

AP 100 VS

Surveyor's Michigan License No. 30096

1995 WAYNE COUNTY REMONUMENTATION PROGRAM

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST
I-3 (SECTION CORNER 2,3,10 & 11)

History compiled by
Peter P. Palczynski, P.S. #20096
AMBIT LAND SURVEYORS, INC.

Continuation of Section "A"

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. # L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER W.P.A.				SET POST	W.O. 16" BEECH 16" 12' ELM 7' ELM TEL. POLE 12' TWIN ELM	S65°W 27 LKS. S32°E 53 LKS. NE 31.31' SE 42.50' SW 55.22' NW 20.64'	1 2 3 4	NOTES = 40.00 CHAINS GONE GONE GONE GONE W.P.A. RECORD: I-3 / I-2 = 2624.15' & 2624.43' I-3 / J-3 = 2621.20' & 2622.17' I-3 / I-4 = 2631.92' & 2631.68' I-3 / H-3 = 2621.55' & 2621.57' I-2 / I-3 / J-3 = 90°19'25" J-3 / I-3 / I-4 = 89°49'10" I-4 / I-3 / H-3 = 90°15'40" H-3 / I-3 / I-2 = 89°36'07"
1981 FEBRUARY 9	PHILIP ENSMINGER R.L.S. #21268		RC #74) L. 21071, P. 659 & 860	I-3	1/2" IRON ROD IN A WAYNE CO. MONUMENT WITH COVER	P.K. NAIL IN D.E. POLE TRAFFIC SIGNAL P.K. NAIL IN D.E. POLE YIELD SIGN	N44°58'E 42.42' S62°15'E 76.98' S42°25'W 72.88' N59°33'W 36.71'	5 6 7 8	M = 41.07' PKWCRC TAG SW FC GONE GONE GONE
1987 MARCH 30	WAYNE COUNTY D.P.S.			I-3 (#31)	5/8" IRON ROD	PKNW SIDE DE POLE/WCRC BRASS TAG CHISELED "X" T/CURB AT JOINT	NE 41.10' SE 74.66'	9 10	M = 41.07' IN SW FACE M = 74.66'
1988 SEPT 13	WAYNE COUNTY D.P.S.			I-3 (#31)	5/8" IRON ROD	CHISELED "X" T/CURB AT JOINT PKNW SIDE DE POLE/WCRC BRASS TAG CHISELED "X" T/CURB AT JOINT	SE 81.80' NE 41.10' SE 74.66'	11 9 10	M = 81.85' M = 41.07' IN SW FACE M = 74.66'
1989 JANUARY 11	RAPHAEL LANDINI, RLS #16933		RC #937	I-3	SET 5/8" IRON ROD N OF WARREN ROAD	PK W/BRASS TAG E. SIDE LAMP POLE PKNW SIDE DE POLE/WCRC BRASS TAG CHISELED "X" T/CURB AT JOINT CHISELED "X" T/CURB AT JOINT PK W/BRASS TAG E. SIDE LAMP POLE	SW 73.23' NE'LY 41.10' SE 74.66' SE 81.80'	12 9 10 11 12	GONE M = 41.07' IN SW FACE M = 74.66' M = 81.85' GONE

FILED DO NOT MAIL