

SURVEY & REMONUMENTATION

DEC 02 1993

RC 1140

LI26985 PA 931

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
 For corners in

WAYNE
 (County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E I-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11/24/93 YCD
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

93 NOV 24 PM 12:08 RC 1140
 FOREST COUNTY REGISTERED RECORDS
 REGISTER OF DEEDS
 REGISTERED DEEDS

I, P.P. Palczynski, in a field survey on 9 November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NANKIN TOWNSHIP

G.L.O. - (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES.
WITNESSES LISTED: POPLAR 10 S2E 1.87(1.2') (GONE) & MAPLE 9 EAST 8.46(5.6') (GONE)
W.P.A. - (1930'S) CROSS ON STONE. WITNESSES SHOWN:

16" ELM	NE	42.02' (GONE)
ED. POLE.	SE	43.19' (GONE)
TEL. POLE.	SW	55.95' (GONE)
M.H.	NW	80.58' (GONE)

C.S.#993, L.18912, P.686, (8-28-74); C.S.#998, L.18942, P.414 (10-14-74). NO L.C.R.C.'S.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD. IN MONUMENT BOX AT CHERRY HILL/MERRIMAN ROADS.
MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:

I-7/J-7: W.P.A. = 2594.50' MEAS. = 2594.42'

W.C.R.C. WITNESS: (4-15-74): MON W/BOX.	W.C.R.C. WITNESS: (11-29-74): MON W/BOX.
DE POLE NE 61.77' (GONE)	8" OAK NE 97.85' (GONE)
DE POLE SE 67.50' (M=67.41')	DE POLE SE 67.45' (M=67.41')
MBT POLE SW 87.00 (GONE)	SE BOLT LT BASE NW 87.75' (GONE)
DE POLE NW 64.67' (GONE)	W.C.R.C. WITNESS: (11-5-75): MON IN BOX.
I-7/I-8: WPA=2620.08' CS#993=2619.82'	ED POLE NE 67.72' (M=67.65')
I-7/H-7: WPA=2676.23' CS#998=2676.16'	ED POLE SE 67.43' (M=67.41')
	ED POLE NW 73.83' (M=73.76')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7: SECTION CORNER 14,15,22 & 23, T2S R9E, FOUND 1/2" REROD. IN MON BOX. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C. REMON. BRASS MARKER AND CAP "PPP PS 30096".

SET NAIL/WCR TAG IN N.W. FACE UTILITY POLE.	N30°E	67.65'
CENTERLINE OF FIRE HYDRANT STEM.	N50°E	93.63'
FOUND P.K. NAIL/WCRC REF PT TAG IN N.E. FACE UTILITY POLE.	S40°E	67.41'
SET NAIL/WCR TAG IN SE FACE UTILITY POLE.	S40°W	74.84'
SET NAIL/WCR TAG IN NE FACE UTILITY POLE.	N35°W	73.76'

Signed by [Signature] Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

2R
HKD

