

DEC 02 1993

RC 1133

LI 26985 PA 929

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 2S R 9E I-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11/24/93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

93 NOV 24 PM 12:08
FOREST COUNTY REGISTER OF DEEDS
RC 1133

P.P. Palczynski, in a field survey on 9 November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NANKIN TOWNSHIP

G.L.O.- (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES.
WITNESSES LISTED: BEECH 12 S48W 36 (23.8') (GONE) & SASSAFRAS 9 N 4 (2.6') (GONE)
W.P.A.- (1930'S) STONE. WITNESSES SHOWN: ED POLE NE 66.24' (GONE)
30" TWIN WALNUT SE 47.83' (GONE)
5" MAPLE SW 27.25' (GONE)
MONUMENT NW 82.33' (GONE)

L.C.R.C.#845, L.22114, P.117. NO C.S.'S ON FILE AT REG. OF DEEDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" REROD. IN CONC. MON. IN MONUMENT BOX AT CARLISLE/MERRIMAN ROADS.

MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:

I-11/I-12: W.P.A. = 2638.35' MEAS. = 2640.01'

L.C.R.C. #845 L.22114, P. 117 (8-17-84) CONCRETE MONUMENT IN BOX.

TOP OF NUT ON FIRE HYDRANT. N28°E 92.97' (GONE)
SPIKE DE POLE. N40°E 66.70' (GONE)
SPIKE, 12" POPLAR. S40°W 64.73' (GONE)
P.K. NAIL TEL. POLE. S80°W 33.55' (M=33.56')
SPIKE, TEL. POLE. N26°W 70.09' (M=70.05')
IRON ROD NEAR SIDEWALK. N40°W 81.72' (M=81.75')



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11:SECTION CORNER 26,27,34 & 35,T2S R9E,FOUND 3/8"REROD/CONC MON IN MON BOX.THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

SET NAIL/WCR TAG IN NORTHWEST FACE UTILITY POLE. N40°E 78.42'
SET NAIL/WCR TAG IN SOUTHWEST FACE UTILITY POLE. S30°E 142.59'
CENTERLINE OF FIRE HYDRANT STEM. S50°W 49.12'
FOUND PK NAIL/WCRC REF PT TAG IN NW FACE UTILITY POLE. S80°W 33.56'
FOUND PK NAIL/WCR TAG IN SW FACE UTILITY POLE. N30°W 70.05'
FOUND IRON ROD NEAR SIDEWALK. N40°W 81.75'

Signed by [Signature]

Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

Handwritten initials: 2R, IKD