

SURVEY & REMONUMENTATION

RC 1364

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE

LI 27059 PA 138

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E I 13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-21-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Raphael J. Landini, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
BEECH 18 S.71E 19 (12.5) (GONE)
W. OAK 30 N 53 E 54 (35.6) (GONE)

WPA (1930S) IRON
ED POLE NE 42.05 (GONE)
14" OAK ENE 43.06 (GONE)
14" MAPLE SE 50.61 (GONE)
12" WALNUT SSE 25.00 (GONE)
IRON W 36.44 (MEAS. 36.48)
18" MAPLE NW 60.00 (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing

WAYNE COUNTY ROAD COMM. IRON (DATE UNKNOWN)
ED POLE NE 42.22 (GONE)
24" MAPLE SE 51.02 (GONE)
12" WALNUT SSE 25.00 (GONE)
IRON W 36.44 (MEAS. 36.48)

WAYNE COUNTY, DPS ROADS 1988
1/2" IRON IN MONUMENT BOX
WCRC TAG DE POLE NE 59.75 (MEAS. 59.75)
WCRC TAG DE POLE SE 60.31 (MEAS. 60.35)
1/2" IRON IN MON. BOX W 36.45 (MEAS. 36.48)
"X" CHISLED SE BOLT
STORE SIGN BASE NW 98.23 (MEAS. 98.28)

LCRC 1974 L. 18725 P 797
MONUMENT IN HAND HOLE
WCRC TAG UTILITY POLE NE 59.88 (MEAS. 59.75)
WCRC TAG UTILITY POLE SE 58.14 (GONE)
WCRC TAG UTILITY POLE SW 90.00 (MEAS. 89.95)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 T2S R9E
STANDARD 4" DIA X 36" CONC. MON. WITH 3/8" IRON ROD; REMON BRASS DISK WITH CAP RJL RLS 16933 IN MON. BOX. SELECTED LOCATION 15 ACCEPTED BY CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNERS.

FOUND WCRC TAG S FACE DE POLE N 38°E 59.75'
FOUND WCRC TAG SW FACE DE POLE S 26°E 60.35'
FOUND WCRC TAG SE FACE DE POLE S 58°W 89.95'
3/8" IRON IN CONC. MONUMENT IN MON. BOX W 36.48'
FOUND "+" CHISLED SE BOLT STORE SIGN BASE N 45° W 98.28'

Signed by [Signature] Date DECEMBER 16, 1993

Surveyor's Michigan License No. 16933

Handwritten initials '2R' and '1147'