

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> <small>(County)</small>	Located In:	Corner Code <u>##</u>
1. Public Land Survey	T <u>2S</u> R <u>9E</u>	<u>J-13</u>
	T _____ R _____	<u>CITY OF WESTLAND</u>
	T _____ R _____	<u>NANKIN TOWNSHIP</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-11-97
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	16	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, PETER P. PALCZYNSKI in a field survey on 1 DECEMBER, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST HICKORY 6" N59°E 4 LKS.
JOSEPH FLETCHER W. ASH 9" N65°W 10 LKS.

\$10.00 DEED

RECORDED
FOREST E. YOUNGLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #42846

SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

SET CONCRETE MONUMENT AND MONUMENT BOX IN CENTERLINE OF VAN BORN ROAD E OF HENRY RUFF IN 54' WIDE ASPHALT PAVEMENT, 87.34' EAST OF FOUND STEEL BAR IN MONUMENT BOX AT J-1, T3S R9E. SET GREY "WAYNE COUNTY REMONUMENTATION CAP" ON CONC. MON. IN MON BOX.

MEASURED:
I-13/J-13/K-13 = 179°54'04" (WPA=179°53'20")
K-13/J-13/I-13 = 180°05'56" (WPA = 180°06'40")

J-13 IN T2S, R9E, IS NOT THE SAME CORNER AS J-1, T3S, R9E.

SURVEY & REMONUMENTATION

MAR 17 1998

SECTION



CORNER POSITION VERIFIED USING 5 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
J-13 / I-13 = 2650.17' (WPA = 2650.29)
J-13 / K-13 = 2637.73' (WPA = 2637.76)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 T2S R9E

SET CONCRETE MONUMENT AND MONUMENT BOX IN CENTERLINE OF VAN BORN ROAD E OF HENRY RUFF IN 54' WIDE ASPHALT PAVEMENT, 87.34' EAST OF FOUND STEEL BAR IN MONUMENT BOX AT J-1, T3S R9E. SET GREY "WAYNE COUNTY REMONUMENTATION CAP" ON CONC. MON. IN MON BOX.	SET NAIL/WCR TAG IN EAST FACE OF UTILITY POLE	N01°E	55.67'
	SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE	S49°E	52.30'
	FD P.K. NAIL/RLS#11192 IN SW FACE OF SAME UTILITY POLE (12) (52.13')	S49°E	52.27'
	CENTERLINE OF FIRE HYDRANT STEM (13) (57.03')	S37°W	57.06'
	SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE	S68°W	93.89'
	FOUND STEEL BAR IN MONUMENT BOX, J-1, T3S, R9E (6) (87.34')	WEST	87.34'
	SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE	N71°W	167.81'
	CENTERLINE OF FIRE HYDRANT STEM (14) (132.3')	N70°W	132.37'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 11 DEC 97

Surveyor's Michigan License No. 30096

2S9EJ-13.DOC

D-100-10-10-20-11 DP1

1997 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST
J-13 (SOUTH 1/4 CORNER SECTION 35)

History compiled by:
Peter P. Paiczynski, P.S. # 30096
AMBIT LAND SURVEYORS, INC.

DATE	COMPANY SURVEYOR JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER			SET POST FOR J-13 T.2S., R.9E., NANKIN.	HICKORY 9" W. ASH 9"	N59°E 4 LKS. N65°W 10 LKS.		NOTES = 40.00 CHAINS
1930'S	W.P.A.			MON (S-35 #160 FOR NANKIN TOWNSHIP T2S, R9E)	10" ELM 30" ELM 16" ELM 14" ELM 14" ELM IRON FOR J-1, T3S, R9E 16" ELM	NE 65.18' NE 66.32' SE 95.20' SE 50.53' SW 72.21' WEST 87.32' NW 53.45'	1 2 3 4 5 6 7	GONE GONE GONE GONE GONE M = 87.34' GONE
11/6/26	W.C.R.C. PLAN & PROFILE TOWNLINE - VAN BORN FILE# A-1-2, P. 13		TOWNLINE - VAN BORN ASST. DIST. #1 ROAD MILE: 7.4 - 8.0 WAYNE CO., MICHIGAN	STONE	NAIL 10" HICKORY NAIL 18" ELM STONE FOR J-1, T3S, R9E NAIL 14" HICKORY	NE 68.85' NE 33.25' WEST 87.4' NW 85.6'	8 9 6 10	W.P.A. RECORD: J-13 / I-13 = 2650.29' J-13 / K-13 = 2637.76' I-13 / J-13 / K-13 = 179°53'20" K-13 / J-13 / I-13 = 180°06'40"
16 SEPT 81	ROSKELLY, JEKABSON & ASSOC., P.C. I. JOHN JEKABSON, P.S. JOB# 81-9-15	P.S. #19836	P/O SW 1/4 SEC 35, T2S, R9E, CITY OF WESTLAND WAYNE COUNTY, MI	P.K. NAIL	NAIL NW DE POLE NAIL SW MBT POLE CL HYDRANT STEEL BAR, J-1, T3S, R9E CL HYDRANT	N60°E 58.08' S50°E 52.13' S35°W 57.03' WEST 87.34' N70°W 132.37'	11 12 13 6 14	GONE M = 52.18' M = 57.06' M = 87.34' M = 132.37'
3/30/95	W.C.R.C. VAN BORN RD		W.C.R.C. VAN BORN RD	NOT SPECIFIED	NOT SPECIFIED			

SECTION
MAR 17 1998
SURVEY &
REMONUMENTATION