

SURVEY & REMONUMENTATION

APR 25 1995

RC 1465

LI27795PA300

\$ 13.00 MISCELLANEOUS RECORDING
22 DEC 94 12:03 P.M. RECEIPT# 358

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E K-3
- 2. Property Controlling in Section S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-21-94 *P.P.*
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, P.P. Palczynski, in a field survey on 7 November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL G.L.O. SURVEYOR: FLETCHER MAY 27, 1817. NANKIN TOWNSHIP
DESCRIPTION OF POST SET FOR CORNER MONUMENT NOT STATED IN FIELD NOTES.
WITNESSES LISTED: BEECH 12 S 24 W 8 (5.2') (GONE) & DO" 10 S 86 E 14 (9.2') (GONE)
W.P.A.-(1930'S) NW-12 HOLE IN CONCRETE WITNESSES SHOWN: GUY POLE SE 63.33' (GONE)
MON SW 84.37' (GONE)
ROAD MRKR NW 50.34' (GONE)
NO SUBSEQUENT R.C. OR C.S. FORMS AT WAYNE CO. REGISTER DEEDS THIS DATE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" IRON PIPE/CONC MON IN MON BOX AT WARREN/MIDDLEBELT RDS. (ASPHALT PVT)
MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:
K-3/K-2: WPA=2623.73'; MEAS=2623.44'; K-3/L-3: WPA=2625.49'; MEAS=2625.58'
K-2/K-3/L-3: WPA=89°54'00"; MEAS=89°53'37"
WCRC SECTION CORNER WITNESS RECORD(12-6-89)
MONUMENT IN BOX

WCRC TAG ON NW SIDE DE POLE	N38°E	68.32' (MEAS=68.37')
WCRC TAG ON NE SIDE DE POLE	S48°E	68.48' (GONE)
"X" CUT ON NW BOLT OF STREET LAMP	S31°W	69.22' (MEAS=69.25')
"X" CUT ON NE BOLT LAMP POLE.	N54°W	81.64' (MEAS=81.71')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3: SECTION CORNER 1,2,11&12, T2S, R9E, FOUND 3/8" IRON PIPE/CONC MON IN MON BOX.
THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

FD PK NAIL/WCRC TAG REF PT IN NORTHWEST FACE UTILITY POLE	N40°E	68.37'
SET NAIL/WCR TAG IN NORTHEAST FACE UTILITY POLE.	S50°E	79.37'
CENTERLINE OF WCRC BENCHMARK BRASS DISC#110-70.	S45°W	79.38'
FOUND "X" ON NORTHWEST BOLT OF LIGHT POLE.	S40°W	69.25'
FOUND IRON PIPE AT WALK INTERSECTION.	S45°W	84.54'
FOUND "X" ON NORTHEAST BOLT OF LIGHT POLE.	N55°W	81.71'

Signed by *[Signature]* Date 22 DEC 94
 Surveyor's Michigan License No. 30096

RC 1465

*2 R
11-D MISC.*