

DEC 22 1998

FILE DO NOT MAIL

SURVEY & REMONUMENTATION

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WAYNE

(County)

Located In:

Corner Code #/

1. Public Land Survey

T 2 S R 9 E

K-6

T R

GARDEN CITY
NANKIN TWP (08)

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. Recorded Plat

5. Private Claims

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-10-98
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Vertical stamp: 64853378232 12/22/1998 08:33AM

PETER P. PALCZYNSKI in a field survey on 1 DECEMBER 1998

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST MAPLE 10" N10°E 20 LKS.
JOSEPH FLETCHER B.O. 9" N89°E 15 LKS.

\$4.00 REMONUMENTATION
\$10.00 DEED

RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #101465

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/2" PIPE IN CONCRETE MON / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MIDDLEBELT RD & MARQUETTE AVE IN 63' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. PLACED 1" PIPE WITH 1/2" REBAR WITH REMON ALUMINUM CAP STAMPED "PPP PS #30096" IN EXISTING PIPE.

MEASURED:
K-5/K-6/K-7 = 179°59'45" (WPA = 179°59'40")
K-7/K-6/K-5 = 180°00'15" (WPA = 180°00'00")

CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
K-6 / K-7 = 2626.00' (2625.40 / 2625.42' WPA)
K-6 / K-5 = 2603.19' (2602.74' / 2602.84' WPA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1-1/2" PIPE IN CONCRETE MON / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MIDDLEBELT RD & MARQUETTE AVE IN 63' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. PLACED 1" PIPE WITH 1/2" REBAR WITH REMON ALUMINUM CAP STAMPED "PPP PS #30096" IN EXISTING PIPE.

FD PK NAIL/WCRC TAG IN SE FACE 12" ASH (4) (R=74.09')
CENTERLINE FIRE HYDRANT STEM (1) (R=71.07')
FOUND CONCRETE MONUMENT
CUT "X" IN SOUTHWEST BOLT OF LIGHT POLE BASE
SET NAIL/WCRC TAG IN NORTHWEST FACE OF UTILITY POLE
FOUND CUT "X" IN NORTH RIM OF SANITARY MH (3) (R=31.71')
FOUND CONCRETE MONUMENT
SET NAIL/WCRC TAG IN NORTHEAST FACE UTILITY POLE



SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by

Signature of Peter P. Palczynski

Date

21 DEC 98

Surveyor's Michigan License No. 30096

2S9EK-6.DOC R LCR 10 4R 2PG U. DPJ

1998 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

History compiled by:
Peter P. Palczynski, P.S. # 30096
AMBIT LAND SURVEYORS, INC.

NANKIN TOWNSHIP, TOWN 2 SOUTH, RANGE 9 EAST
K-6 (SECTION CORNER 13 & 14)

| DATE | COMPANY SURVEYOR JOB # | P.S. # | P.A. 74 L.C.R.C. | LOCATION OF SURVEY | MONUMENT DESCRIPTION | WITNESSES | BEARING & DISTANCE | ID # | COMMENT |
|-----------|--|--------|------------------|----------------------------------|----------------------------|--|--|-------------------|--|
| 1816 | G.L.O. | | | | SET POST | MAPLE 10" | N10°E 20 LKS | | NOTES = 40.00 CHAINS |
| 1930'S | JOSEPH FLETCHER W.P.A. | | | | IRON (W-13 #76) | B.O. 9" HYDRANT M.H. COVER M.H. COVER | N89°E 15 LKS. NE 71.07' SE 64.03' NW 31.71' | 1 2 3 | MEAS = 71.04' GONE MEAS = 31.71' |
| 1924 | CHARLES E KNIGHT REG. CIVIL ENGINEER | | | NE 1/4 SECTION 14 T2S R 9E | NOT STATED | NOT STATED | | | W.P.A. RECORD: K-6/K-7 = 2625.40' / 2625.42' K-6/K-5 = 2602.74' / 2602.84' K-5/K-6/K-7 = 179° 59' 40" K-7/K-5/K-5 = 180° 00' 00" |
| 1924 | CHARLES E KNIGHT REG. CIVIL ENGINEER | | | NW 1/4 SECTION 13 T2S R9E | NOT STATED | NOT STATED | K-6 / K5 = 2602.75' | | MEAS = 2603.19' |
| 15 APR 25 | H. F. CUSHING, R.L.S. | | | NW 1/4 SECTION 13 T2S R9E | NOT STATED | NOT STATED | | | |
| 17 SEP 52 | MASON L. BROWN REG. CIVIL ENGINEER | | | SE 1/4 SECTION 14 T2S R9E | NOT STATED | NOT STATED | | | |
| 6 DEC 89 | WAYNE COUNTY OFFICE OF PUBLIC SERVICES | | | SECTION 13 CORNER WITNESS RECORD | MON IN BOX | WCRC TAG SE 14" TREE WCRC TAG SW U POLE "X" SE COR CONC BASE SIGNAL WCRC TAG NE DE POLE NOT STATED | 37° NE 74.09' 52° SE 56.72' 52° SW 53.18' 53° NW 51.97' | 4 5 6 7 | MEAS = 74.01' GONE GONE GONE |
| 1 MAR 90 | THOMAS L. GILMORE RLS #16930 | | | SE 1/4 SECTION 14 K-5 | NOT STATED | FD PKWASHER SE 12" TREE FD PKWASHER SW U. POLE FD PK IN TRAFFIC SIGN BASE FD PY NAILWASHER SW U POLE | N45°E 74.04' S40°E 56.69' S45°W 57.43' N45°W 57.73' | 4 8 9 10 | MEAS = 74.01' GONE GONE GONE |
| 21 SEP 92 | MARTIN C DUNN PS #30081 | | | RC 1056 L.26064 P.605 | FOUND IRON PIPE IN MON BOX | | | | |

SURVEY & REMONUMENTATION

MAR 02 1999

SECTION

VKN-K-S.DOC