

DEC 02 1993

RC 1132

LI 26985 PA 923

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County) Located In: Corner Code -#
1. Public Land Survey T 2S R 9E K-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11/24/93 NCA
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

RC 1132

P.P. Palczynski, in a field survey on 4 October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A black dot is present at the intersection of column K and row 11.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.- (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES.
WITNESSES LISTED: BEECH 16 S79E 20 (13.2') (GONE) & SNG. 6 N30E 24 (15.8') (GONE)
W.P.A.- (1930'S) IRON SET. WITNESSES SHOWN: 6" ELM NE 19.15' (GONE)
TEL. POLE SE 45.04' (GONE)
TOP OF HYDRANT SW 51.14' (GONE)

NANKIN TOWNSHIP

NO SUBSEQUENT L.C.R.C. OR C.S. FORMS AT WAYNE COUNTY REGISTER OF DEEDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN CONC. MON. IN MONUMENT BOX AT MIDDLEBELT/CARLYSLE ROADS.

MEASURED DISTANCE FOR COMPARISON TO W.P.A. RECORDS:

K-11/K-12: W.P.A. = 2631.99' MEAS. = 2631.83'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11: SECTION CORNER 25, 26, 35 & 36, T2S R9E, FOUND 3/4" IRON PIPE IN CONC. MON./MON. BOX.
THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".
FOUND PK NAIL/WCRC REF PT TAG IN S FACE UTILITY POLE. N55°E 67.01'
FOUND PK NAIL IN NW FACE 30" ELM. N35°E 63.75'
FOUND NAIL/WCRC REF PT TAG IN NE FACE UTILITY POLE. S40°E 58.54'
SET NAIL/WCR TAG IN NW FACE UTILITY POLE. S50°W 49.67'
FOUND NAIL/WCRC REF PT TAG IN N FACE UTILITY POLE. N65°W 96.28'
FOUND IRON PIPE. N45°W 99.01'

Signed by [Signature] Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

Handwritten initials: 2R, HKD