

DEC 22 1998  
FILE DO NOT MAIL

SURVEY & REMONUMENTATION

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

WAYNE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 2 S R 9 E

L-7  
GARDEN CITY  
NANKIN TWP (08)

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-10-98  
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

58485384032 12/22/1998 09:35AM

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

PETER P. PALCZYNSKI in a field survey on 1 DECEMBER, 1998

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST POPLAR 12" N83°W 16 LKS.  
JOSEPH FLETCHER MAPLE 10" S54°E 5 LKS.

\$4.00 REMONUMENTATION  
\$10.00 DEED

RECORDED  
FOREST E. YOUNGLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
Receipt #101465

SEE BACK OF THIS SHEET (NEXT PAGE)  
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE IN CONC MON / MONUMENT BOX, AT CENTERLINE INTERSECTION OF CHERRY HILL RD & HARRISON RD IN 61' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS, SET 1/2" STEEL BAR IN EXISTING CONC MON WITH REMON ALUMINUM CAP STAMPED "PPP PS #30096"

MEASURED:  
K-7/L-7/M-7 = 179°12'58"  
(WPA = 179°11'50")  
M-7/L-7/K-7 = 180°47'02"  
(WPA = 180°48'20")  
L-8/L-7/K-7 = 91°14'40"  
(91°17' PLAT)  
M-7/L-7/L-8 = 89°32'08"  
(89°32' PLAT)

CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:  
L-7 / M-7 = 2697.29' (2697.27 / 2697.24' WPA)  
L-7 / K-7 = 2626.45' (2626.67' / 2626.60' WPA)  
L-7 / L-8 = 2617.97' (2617.40' PLAT)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7, T2S, R9E  
FOUND 1" IRON PIPE IN CONC MON / MONUMENT BOX, AT CENTERLINE INTERSECTION OF CHERRY HILL RD & HARRISON RD IN 61' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS, SET 1/2" STEEL BAR IN EXISTING CONC MON WITH REMON ALUMINUM CAP STAMPED "PPP PS #30096"

SET NAIL/WCR TAG IN WEST FACE OF 15" LOCUST CUT "X" IN SOUTH BASE OF TRAFFIC CONTROL POLE  
SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE  
NORTHEAST HOUSE CORNER #28419  
FOUND CONCRETE MONUMENT  
SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE  
CENTERLINE FIRE HYDRANT STEM

N07°E 94.40'  
N33°E 58.30'  
S31°E 49.60'  
S33°W 100.00'  
S36°W 73.10'  
N49°W 67.61'  
N32°W 75.08'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by

*[Signature]*

Date

21 DEC 98

Surveyor's Michigan License No. 30096

1998 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST  
L-7 (SECTION CORNER 13 & 24)

History compiled by:  
Peter P. Palczynski, P.S. # 30096  
AMBIT LAND SURVEYORS, INC.

SURVEY &  
REMONUMENTATION

MAR 02 1999

SECTION

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER				SET POST	POPLAR 12' MAPLE 10'	N83°W 16 LKS S54°E 5 LKS		NOTES = 40.10 CHAINS
1930'S	W.P.A.				STONE (N-24 #80)	12' MAPLE TWIN TREE 30" OAK	N 46.35' S 58.05' NW 44.95'	1 2 3	GONE GONE GONE
									W.P.A. RECORD: L-7/M-7 = 2697.27' / 2697.24' L-7/K-7 = 2626.67' / 2626.60' K-7/L-7/M-7 = 179° 11' 50" M-7/L-7/K-7 = 180° 48' 20"
1924	M. F. FISHER REG. CIVIL ENG & SURVEYOR			NE 1/4 SECTION 24 T2S R 9E	NOT STATED	NOT STATED	L-7 / L-8 = 2617.40' / PLAT		MEAS = 2617.97'
18 AUG 24	H. BAKER REG. CIVIL ENG & SURVEYOR			NW 1/4 SECTION 24 T2S R9E	NOT STATED	NOT STATED	M-7/L-7/L-8 = 89°32' 30"/PLAT L-8/L-7/K-7 = 91° 17' / PLAT		MEAS = 89°32' 08" MEAS = 91° 14' 20"
14 MAY 25	H. F. CUSHING, R.L.S.			SW 1/4 SECTION 13 T2S R9E	NOT STATED	NOT STATED			L-6 NOT FOUND
30 DEC 55	PATE & HIRN EDWIN PATE RLS			S 1/2 SECTION 13 T2S R9E	NOT STATED	NOT STATED			

NKN-L-7.DOC