

**FILE DO NOT MAIL**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>WAYNE</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>2 S</u> R <u>9 E</u>	<u>L-11</u>
	T _____ R _____	<u>CITY OF INKSTER</u>
	T _____ R _____	<u>NANKIN TOWNSHIP</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-11-97 *DPJ*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

I, PETER P. PALCZYNSKI in a field survey on 1 DECEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1816 G.L.O. - SET POST BEECH 12" S47°E 9 LKS.  
JOSEPH FLETCHER SUG. N07°W 13 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE)  
FOR CONTINUATION OF SECTION "A"

\$4.00 REMONUMENTATION  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
Receipt #42846

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET CONCRETE MONUMENT AND MONUMENT BOX AT CENTERLINE OF CARLYSLE AVE. & HARRISON AVE. INTERSECTION, 37' WIDE CONCRETE PAVEMENT WITH CONC CURBS. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096 ON CONC MONUMENT IN MON BOX.

MEASURED:  
M-11/L-11/L-12 = 89°58'44"  
(WPA=90°00'30")  
M-12/M-11/L-11 = 89°59'51"  
(WPA=89°58'00")  
L-12/M-12/M-11 = 90°19'26"  
(WPA=90°20'30")  
L-11/L-12/M-12 = 89°41'59"  
(WPA=89°41'00")

**SURVEY & REMONUMENTATION**

MAR 17 1998

SECTION

CORNER POSITION VERIFIED USING 2 FOUND R.O.W. IRONS AND SUPPORTING W.P.A. SURVEY INFORMATION, EVALUATING RECORD DISTANCES AND ANGLES.

MEASURED:  
L-11/M-11 = 2642.63' (WPA 2642.38 / 2642.48)  
L-11/L-12 = 2648.00 (WPA = 2647.99)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11, T2S, R9E	SET NAIL/WCR TAG IN WEST FACE OF UTILITY POLE	N22°E	128.98'
SET CONCRETE MONUMENT AND MONUMENT BOX AT CENTERLINE OF CARLYSLE AVE. & HARRISON AVE. INTERSECTION, 37' WIDE CONCRETE PAVEMENT WITH CONC CURBS. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096 ON CONC MONUMENT IN MON BOX.	FOUND 1" IRON PIPE	N36°E	73.10'
	SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE	S35°E	42.62'
	SOUTHEAST CORNER OF BUILDING #3710	S33°W	68.83'
	BACK OF CONCRETE CURB	WEST	18.5'
	NORTHEAST CORNER OF BUILDING #3710	N85°W	37.99'
	CENTERLINE OF FIRE HYDRANT STEM	N38°W	75.68'
	FOUND 3/4" IRON PIPE	N27°W	74.60'
	SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE	N22°W	66.85'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *PP* Date 11 DEC 97

Surveyor's Michigan License No. 30096

1997 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

History compiled by:  
Peter P. Palczynski, P.S. # 30096  
AMBIT LAND SURVEYORS, INC.

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST  
L-11 SECTION CORNER 25 & 36)

DATE	COMPANY SURVEYOR JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER			SET POST FOR L-11 T.2S., R.9E., NANKIN.	BEECH 12" SUG.	S47°E 9 LKS. N07°W 13 LKS		NOTES = 39.90 CHAINS
1930'S	W.P.A.			IRON (N-36 #132 FOR NANKIN TOWNSHIP T2S, R9E)	ED POLE IRON IRON	SE 42.82' NW 33.85' NW 79.18'	1 2 3 4	GONE GONE GONE GONE W.P.A. RECORD: L-11 / M-11 = 2642.38' / 2642.48' L-11 / L-12 = 2647.99' M-11 / L-11 / L-12 = 90°00'30" L-12 / L-11 / K-11 = 89°46'10"
3/28/24	LEE D. ZIMMERMAN REGISTERED CIVIL ENG	"INKSTER GARDENS SUB" L.48,P.73	W 1/2 OF NE 1/4 SEC 36 T2S, R9E, NANKIN TWP.	IRON	NOT STATED			PLAT RECORD: M-11 / L-11 / L-12 = 89°56' L-11 / L-12 = 2648.00'

NKN-L-11.DOC

SURVEY &  
REMONUMENTATION  
MAR 17 1998  
SECTION