

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L129358 PA636

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2 S</u> R <u>9 E</u>	<u>L-13</u>
	T _____ R _____	<u>CITY OF WESTLAND</u>
	T _____ R _____	<u>NANKIN TOWNSHIP</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: Dec. 18, 1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23						
9											
10	30	29	28	27	26						
11											
12	31	32	33	34	35						
13											

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST B. ASH 12' N87°E 14 LKS.
 JOSEPH FLETCHER DO. 10' S53°E 27 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE)
 FOR CONTINUATION OF SECTION "A"

\$ 10.00 DEED
 26 DEC 96 8:22 A.M. RECEIPT# 1B
 RECORDED
 FOREST E. REMONUMENTATION REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN MONUMENT BOX 3' NORTH OF PAINTED CENTERLINE OF VAN BORN RD ASPHALT PAVEMENT. SET 3/8" STEEL BAR WITH WAYNE COUNTY REMON BRASS WASHER WITH PLASTIC CAP "PPP-PS - #30096" IN 3/4" IRON PIPE.
 MEASURED:
 K-13/L-13/M-13 = 180°00'30"
 M-13/L-13/K-13 = 179°59'30"
 L-13 IN T2S, R9E, IS NOT THE SAME CORNER AS L-1, T3S, R9E.

CORNER POSITION VERIFIED USING 1 WITNESS AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
 L-13 / M-13 = 2637.24' (R=2637.52')
 L-13 / K-13 = 2639.86' (R=2639.86')



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13, T2S, R9E	FOUND CONCRETE MONUMENT (HIT)	NORTH	59.89'
FOUND 3/4" IRON PIPE IN MONUMENT BOX 3' NORTH OF PAINTED CENTERLINE OF VAN BORN RD ASPHALT PAVEMENT. SET 3/8" STEEL BAR WITH WAYNE COUNTY REMON BRASS WASHER WITH PLASTIC CAP "PPP-PS - #30096" IN 3/4" IRON PIPE.	FOUND CUT "X" IN SOUTH RIM OF GV&W CENTERLINE OF FIRE HYDRANT STEM	N03°E	44.94'
	SET NAIL/WCR TAG IN SOUTH FACE OF UTILITY POLE	N36°E	57.88'
	SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE	N72°E	123.39'
	FOUND PK NAIL/WCRC REF TAG IN NW FACE OF UTILITY POLE	S48°E	65.47'
	FOUND CONCRETE MONUMENT / MONUMENT BOX (L-1) (4) (R=62.62')	S50°W	80.77'
	SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE	WEST	62.70'
	FOUND P.K. NAIL IN NORTHEAST FACE OF UTILITY POLE	N54°W	68.25'
		N50°W	67.82'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by P.P.P. Date 23 DEC 96

1996 WAYNE COUNTY REMONUMENTATION PROGRAM

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST
L-13 (SOUTH 1/4 CORNER SECTION 36)

History compiled by:
Peter P. Palczynski, P.S. # 30096
AMBIT LAND SURVEYORS, INC.

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER				SET POST FOR L-13 T2S, R3E, NANKIN.	B. ASH 12" DO. 10"	N87°E 14 LKS. S63°E 27 LKS.	1	NOTES = 40.00 CHAINS
1930S	W.P.A.				IRON (S-36 #158 FOR NANKIN TOWNSHIP T2S, R9E)	6" ELM 16" OAK IRON FOR L-1 ED POLE	SE 52.62' SW 71.9' WEST 62.62' NW 64.32'	2 3 4	GONE GONE M = 62.70' GONE

W.P.A. RECORD:

- L-13 / M-13 = 2637.52'
- L-13 / K-13 = 2639.86'
- K-13 / L-13 / M-13 = 180°00'20"
- M-13 / L-13 / K-13 = 179°59'40"