

78400385LS 12/22/98 08:40AM

DEC 22 1998 4

FILE DO NOT MAIL

MAR 02 1999

LAND CORNER RECORDATION CERTIFICATE SECTION
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE (County) Located In: Corner Code #/
1. Public Land Survey T2S R9E M-2 WESTLAND NANKIN TWP (08)
2. Property Controlling S T R
3. Miscellaneous S T R
Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-10-98 DPJ
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

PETER P. PALCZYNSKI in a field survey on 1 DECEMBER, 1998
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1816 G.L.O. - SET POST BEECH 12" S72°W 5 LKS.
JOSEPH FLETCHER SUG 6" N48°E 11 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF INKSTER ROAD IN 50' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. SET BRASS WAYNE COUNTY REMON WASHER STAMPED "PPP PS #30096" ON CONC. MON.
MEASURED: M-1/M-2/M-3 = 180°01'02" (WPA = 180°02'40") M-3/M-2/M-1 = 179°58'58" (WPA = 179°57'20")
M-2 IN T2S, R9E, IS NOT THE SAME CORNER AS A-2, T2S, R10E.

CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED: M-2 / M-1 = 2650.06' (2650.48' WPA) M-2 / M-3 = 2651.54' (2650.75' WPA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2, T2S, R9E
FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF INKSTER ROAD IN 50' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. SET BRASS WAYNE COUNTY REMON WASHER STAMPED "PPP PS #30096" ON CONC. MON.
CUT "X" ON EAST BOLT OF HAND RAIL ON BRIDGE
SET NAIL/WCR TAG IN SOUTH FACE OF UTILITY POLE
FOUND IRON PIPE
SET NAIL/WCR TAG IN SOUTH FACE OF 36" MAPLE (2) (R=63.13')
FOUND CONCRETE MONUMENT IN MON BOX - A2 (4) (R=7.66')
SET NAIL/WCR TAG IN SOUTH FACE OF UTILITY POLE
CUT "X" ON WEST BOLT OF HAND RAIL ON BRIDGE
N19°E 88.52'
S84°E 46.51'
S82°E 60.11'
S80°E 64.17'
SOUTH 7.55'
S76°W 50.45'
N19°W 88.55'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 21 DEC 98

Surveyor's Michigan License No. 30096

2S9EM-2.DOC R LCR 10 4R 2PG U. J.P.J.

Grid table with columns A-M and rows 1-11. Contains numerical values and stamps: \$4.00 REMONUMENTATION, \$10.00 DEED, RECORDED FOREST E. YOUNGLOO, REGISTER OF DEEDS WAYNE COUNTY, MI Receipt #101465



Continuation of Section "A"

1998 WAYNE COUNTY REMONUMENTATION PROGRAM

History compiled by:
 Peter P. Palczynski, P.S. # 30096
 AMBIT LAND SURVEYORS, INC.

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST
 M-2 (E. 1/4 CORNER OF SECTION 1)

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER				SET POST	BEECH 12' SUG 6'	S72°W 5 LKS N48°E 11 LKS.		NOTES = 40.00 CHAINS
1930 S	W.P.A.				CROSS SET (E-1 #26 FOR NANKIN TOWNSHIP T2S, R9E)	SE COR BRIDGE PIER 24' MAPLE 12' APPLE CROSS (A-2) 30' MAPLE	NE 50.22' EAST 63.13' SE 66.13' SOUTH 7.66' WEST 76.25'	1 2 3 4 5	GONE MEAS = 64.17 GONE GONE GONE
3 AUGUST 78	BOYD ARTHURS, RLS JOB #112-78		CS 1521 L 20316 P832-833	SW 1/4 SECTION 6 T2S R 10E, DEARBORN HEIGHTS	WCRC MON	BENT MON IN WCRC HANDHOLE	SOUTH 7.71'	4	MEAS = 7.55'

W.P.A. RECORD:
 M-2/M-1 = 2650.48
 M-2/M-3 = 2650.75'
 M-1/M- 2/M-3 = 180° 02' 40"
 M-3/M- 2/M-1 = 179° 57' 20"

SURVEY &
 REMONUMENTATION

MAR 02 1999

SECTION

NKN-M-2.DOC