

DEC 02 1993

COMMISSION

RC 1134

LI26985 PA 925

93 NOV 24 PM 12:08
FOREST COUNTY REGISTERED PROFESSIONAL SURVEYORS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in WAYNE (County)

Located In: Corner Code: #

- 1. Public Land Survey T 2S R 9E M-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11/24/93 MCA WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

RC 1134

P.P. Palczynski in a field survey on 9 November 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-12. Contains numbers 1-36.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NANKIN TOWNSHIP

G.L.O.- (1830'S) DESCRIPTION OF CORNER MONUMENT NOT STATED IN FIELD NOTES. WITNESSES LISTED: BEECH 10 N58W 37 (24.4') (GONE) & DO." 12 S75W 41 (27.1') (GONE) W.P.A.- (1930'S) BRASS PIN. WITNESSES SHOWN: CROSS N 23.6' (GONE) NO CALL NE 101.25' ANCHOR POST SE 47.10' (GONE) TOP OF HYD. SW 76.52' (GONE) RD. SIGN POST NW 49.81' (GONE) NO SUBSEQUENT L.C.R.C. OR C.S. FORMS AT WAYNE CO. REG. DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" REROD. IN CONC. MON. IN MONUMENT BOX AT WARREN/ INKSTER ROADS. MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS: M-3/L-3: W.P.A. = 2624.95' MEAS. = 2624.88' WAYNE COUNTY ROAD COMMISSION (3-19-75): "MON IN BOX"

NW COR SEC 7 DEARBORN N 23.67' (MEAS. 23.68') ED. POLE NE 76.92 (GONE) ED. POLE SE 67.10' (MEAS. 66.99') ED. POLE NW 64.20' (MEAS. 64.15')



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3: SECTION CORNER 1 & 12, T2S R9E, FOUND 3/8" REROD/CONC MON IN MON BOX. THE SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096". FOUND CONCRETE MONUMENT IN MONUMENT BOX. NORTH 23.68' FOUND WCRC BRASS DISC BM#120-70 - CENTER. N20°E 97.41' SET NAIL/WCR TAG IN NW FACE UTILITY POLE. N35°E 76.92' FOUND PK NAIL/WCRC REF PT TAG IN SW FACE UTILITY POLE. S50°E 66.99' SET NAIL/WCR TAG IN SE FACE UTILITY POLE. S40°W 69.34' FOUND PK NAIL/WCRC REF PT TAG IN NE FACE UTILITY POLE. N25°W 64.14'

Signed by [Signature] Date 15 NOVEMBER 1993

Surveyor's Michigan License No. 30096

2K IKD