

**FILE DO NOT MAIL**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>9E</u>	<u>M-4</u>
	T _____ R _____	<u>GARDEN CITY</u>
	T _____ R _____	<u>NANKIN TOWNSHIP</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with  
**ACT 345, P.A. 1990**  
APPROVED ON: 12-11-97 *DPJ*  
**WAYNE COUNTY REMONUMENTATION**  
**PEER GROUP COMMITTEE**  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, **PETER P. PALCZYNSKI** in a field survey on 1 DECEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

1816 G.L.O. - SET POST BEECH 10" N11°E 12 LKS.  
JOSEPH FLETCHER DO 12" S20°E 20 LKS.

**\$10.00 DEED**  
RECORDED  
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
Receipt #42846

SEE BACK OF THIS SHEET (NEXT PAGE)  
FOR CONTINUATION OF SECTION "A"

**\$4.00 REMONUMENTATION**

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MAPLEWOOD AVE. & INKSTER ROAD IN 50' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096" ON CONC. MON.

MEASURED:  
M-3/M-4/M-5 = 180°02'33"  
(WPA = 180°02'30"  
180°02'15")  
M-5/M-4/M-3 = 179°57'27"  
(WPA = 179°57'45"  
179°57'30")

M-4 IN T2S, R9E, IS THE SAME CORNER AS A-4, T2S, R10E.

**SURVEY & REMONUMENTATION**

**MAR 17 1998**

**SECTION**



CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:  
M-4 / M-5 = 2566.60' (2566.25'/2566.52' WPA)  
M-4 / M-3 = 2700.27' (2700.37'/2700.40' WPA)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

M-4, T2S, R9E & A-6, T2S, R10E, FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MAPLEWOOD AVE. & INKSTER ROAD IN 50' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096" ON CONC. MON.

SW CORNER BRICK WALL / SIGN  
FOUND IRON PIPE  
FOUND NAIL/WCRC REF PT IN SW FACE UTILITY POLE  
CENTERLINE FIRE HYDRANT STEM  
FOUND STEEL ENCASED CONCRETE MONUMENT  
FOUND STEEL ENCASED CONCRETE MONUMENT  
SET NAIL/WCRC TAG IN NE FACE OF UTILITY POLE  
FOUND STEEL ENCASED CONCRETE MONUMENT  
CENTERLINE FIRE HYDRANT STEM

N55°E 72.95'  
S53°E 74.67'  
S44°E 51.29'  
S43°E 61.60'  
S55°W 73.21'  
N61°W 91.25'  
N53°W 60.92'  
N43°W 87.73'  
N21°W 127.38'

**SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.**

Signed by *PP* Date 11 DEC 97

Surveyor's Michigan License No. 30096  
2S9EM-4.DOC

*DP-1*

**1997 WAYNE COUNTY REMONUMENTATION PROGRAM**

Continuation of Section "A"

M-4 (E. 1/4 CORNER OF SECTION 12 & W. 1/4 CORNER OF SECTION 7, T2S, R10E, A-4)  
 NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST  
 Peter P. Palczynski, P.S. # 30096  
 AMBIT LAND SURVEYORS, INC.

History compiled by:

COMPANY  
 SURVEYOR  
 JOB #

P.A. 74  
 L.C.R.C.

LOCATION  
 OF SURVEY

MONUMENT  
 DESCRIPTION

WITNESSES

BEARING  
 & DISTANCE

ID #

COMMENT

DATE	COMPANY SURVEYOR JOB #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER W.P.A.			SET POST	BEECH 10" DO 12"	N11°E 12 LKS S20°E 20 LKS.		NOTES = 40.00 CHAINS
1930'S				IRON (E-12 #52 FOR NANKIN TOWNSHIP T2S, R9E)	3" ELM CONC CULVERT TWIN APPLE	NE 48.2' SE 171.08' NW 34.45'	1 2 3	GONE GONE GONE
				IRON (W-7 # 40 FOR DEARBORN TOWNSHIP T2S, R10E)	3" ELM CONC CULVERT TWIN APPLE	NE 48.2' SE 171.08' NW 34.45'	1 2 3	GONE GONE GONE

W.P.A. RECORD:

M-4M-5 = 2566.25' / 2566.52'  
 M-4M-3 = 2700.37' / 2700.40'  
 M-3M-4M-5 = 180° 02' 30" / 180° 02' 15"  
 M-5M-4M-3 = 179° 57' 45" / 179° 57' 30"

NKN-M-4.DOC

SURVEY &  
 REMONUMENTATION  
 MAR 17 1998  
 SECTION