

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

RC 1469

L127795PA304
 \$ 13.00 MISCELLANEOUS RECORDING
 22 DEC 94 12:05 P.M. RECEIPT# 35B
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

WAYNE

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 9E M-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 11-21-94 *DD*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, P.P. Palczynski, in a field survey on 7 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 ORIGINAL G.L.O. SURVEYOR: FLETCHER - MAY 27, 1817.
 DESCRIPTION OF POST SET FOR CORNER MONUMENT: NOT STATED IN FIELD NOTES.
 WITNESSES: ELM 20 N 86 W, 33(21.8)(GONE) & LYNN 9 S 53 E, 13(8.6)(GONE)
 G.L.O. NOTES - T2S, R10E: "COR SEC 12, 13 T2S, R9E"(NO FALLING NOTED)
 W.P.A.-(1930'S)NE-13 IRON,WITNESSES SHOWN:TEL POLE SE 52.47' (GONE)
 ROAD MRKR NW 47.23'(GONE) BASE FIRE HYD SW 77.5' (MEAS=77.68')
 W.P.A.-(1930'S) NW-18, T2S, R10E, SAME WITNESSES TO IRON, AS SHOWN ABOVE.
 C.S.#134, L18022, P53; C.S.#135, L18022,P54; R.C.#45, L18022,P7.

NANKIN TOWNSHIP

RC 1469

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND BRASS CAP "MDSHT RLS 13589 ON CONCRETE MONUMENT IN MONUMENT BOX. (CONC. PVT)
 AT INKSTER ROAD AND FORD ROAD INTERSECTION.
 MEASURED DISTANCES FOR COMPARISON TO W.P.A. RECORDS:
 M-5/M-4:W.P.A. = 2566.52' MEAS=2566.58' M-5/M-6:W.P.A.=2640.14' MEAS=2640.31'
 M-5/L-5:W.P.A. = 2660.17' MEAS=2660.49' M-5/B-5:W.P.A.=2636.36' MEAS=2636.22'
 M-4/M-5/B-5:WPA=90°29'00" MEAS=90°29'11" B-5/M-5/M-6:WPA=89°33'00"MEAS=89°33'19"
 M-6/M-5/L-5:WPA=89°31'10" MEAS=89°30'51" L-5/M-5/M-4:WPA=90°26'45"MEAS=90°26'30"
 R.C.#45 L18022, P7, (3-22-72) FOUND IRON BAR IN MONUMENT BOX.
 M.S.H.D. NAIL IN EDISON POLE N41°W 59.60' (GONE)
 W.C.R.C. NAIL IN EDISON POLE S53°E 64.05' (GONE)
 M.S.H.D. NAIL IN EDISON POLE S44°W 74.15' (GONE)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-5:SECTION CORNER 12 & 13 T2S R9E FOUND BRASS CAP ON CONCRETE MON IN MON BOX.THE
 SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY
 PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE
 ORIGINAL CORNER. NO W.C.REMON. BRASS MARKER OR CAP "PPP PS 30096" PLACED.
 SET NAIL/WCR TAG IN SOUTHEAST FACE OF UTILITY POLE. N10°E 158.69'
 SOUTHWEST CORNER OF BUILDING #27350. N45°E 85.82'
 FOUND NAIL/MDSH TAG IN NORTHEAST FACE OF UTILITY POLE. S53°E 83.34'
 FOUND NAIL/MDSH TAG IN SOUTHEAST FACE OF UTILITY POLE. S40°W 80.92'
 CENTERLINE OF BRASS DISC WCRC BENCHMARK #120-80. S45°W 80.95'
 SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE. N45°W 74.70'

2R
 11-D-MISC

Signed by [Signature] Date 22 DEC 94

Surveyor's Michigan License No. 30096