

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 29358 PA 634

For corners in

<u>WAYNE</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>2 S</u> R <u>9 E</u>	<u>M-10</u>
	T _____ R _____	<u>INKSTER</u>
	T _____ R _____	<u>NANKIN TOWNSHIP</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with ACT 345, P.A. 1990

DPJ

APPROVED ON: DEC 18, 1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST B.O. 12" N42°W 36 LKS.
 JOSEPH FLETCHER DO. 10" S71°W 27 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE)
 FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF INKSTER ROAD ASPHALT PAVEMENT. SET 3/8" STEEL BAR WITH GRAY "WAYNE COUNTY REMONUMENTATION" CAP ON 3/8" STEEL BAR.

MEASURED:
 M-9/M-10/M-11 = 180°01'19"
 M-11/M-10-M-9 = 179°58'41"

M-10 IN T2S, R9E, IS THE SAME CORNER AS A-10, T2S, R10E.

CORNER POSITION VERIFIED USING 2 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
 M-10/ M-9 = 2633.85' (R=2634.26'/2634.23')
 M-10/ M-11 = 2637.18' (R=2636.19'/2636.53')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 T2S, R9E & A-10, T2S, R10E, FOUND 3/4" IRON PIPE IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF INKSTER ROAD ASPHALT PAVEMENT. SET 3/8" STEEL BAR WITH GRAY "WAYNE COUNTY REMONUMENTATION" CAP ON 3/8" STEEL BAR.	FOUND NAIL/WASHER RLS #14759 IN NW FACE OF UTILITY POLE	N29°E	61.06'
	SET NAIL/WCR TAG IN NORTHWEST FACE OF SAME UTILITY POLE	N29°E	61.08'
	NORTHWEST CORNER OF CATCH BASIN RIM	S27°E	43.25'
	SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE	S09°E	188.12'
	SET NAIL/WCR TAG IN SOUTHEAST FACE OF UTILITY POLE	S25°W	69.33'
	SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE	N09°W	177.33'

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

\$ 10.00 DEED
 26 DEC 96 8:22 A.M. RECEIPT# 1B
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION



SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by _____

Date 23 DEC 96

Surveyor's Michigan License No. 30096
 2S9EM-10DOC

41
10
DPJ

Continuation of Section "A"

1996 WAYNE COUNTY REMONUMENTATION PROGRAM

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST
 M-10 (E. 1/4 CORNER OF SECTION 25 & W. 1/4 CORNER OF SECTION 30, T2S, R10E, A-10) **AMBIT LAND SURVEY**

History compiled

Peter P. Palczynski, P.

BEARING & DISTANCE ID # COMMENT

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	GLO. JOSEPH FLETCHER				SET POST	B.O. 12"	N42°W 36.1KS		NOTES = 40.00 (
1930'S	W.P.A.				IRON	DO. 10"	S71°W 27 LKS.		
					(E-25 #130 FOR NANKIN TOWNSHIP T2S, R9E)	48" MAPLE	NE 22.04'	1	GONE
						24" MAPLE	SE 33.42'	2	GONE
						LIGHT POLE	SW 28.70'	3	GONE

IRON	48" MAPLE	NE 22.04'	1	GONE
(W-30 # 118 FOR DEARBORN TOWNSHIP T2S, R10E)	24" MAPLE	SE 33.42'	2	GONE
	LIGHT POLE	SW 28.70'	3	GONE

W.P.A. RECORD
 M-10M-9 = 2634;
 M-10M-11 = 263K
 M-9M-10M-11 =
 M-11M-10M-9 =