

**SURVEY &
REMONUMENTATION**

RC 1472

APR 25 1995

L127795PA307

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 13.00 MISCELLANEOUS RECORDING
22 DEC 94 12:06 P.M. RECEIPT# 35B
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in
WAYNE

Located In: Corner Code #/

- (County)
1. Public Land Survey T 2S R 9E M-11
T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-21-94 *DPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

P.P. Palczynski

7 November 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NANKIN TOWNSHIP

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL G.L.O. SURVEYOR: FLETCHER - MAY 27, 1817.

DESCRIPTION OF POST SET FOR CORNER MONUMENT NOT STATED IN FIELD NOTES.

WITNESSES LISTED: BEECH 6 N 85 W 17 (11.2') (GONE) & DO" 12 S 20 W 12 (7.9') (GONE)

G.L.O. NOTES - T2S, R10E: COR SEC 25, 36 T2S, R9E (NO FALLING NOTED)

W.P.A.-(1930'S) NE-36 IRON. WITNESSES SHOWN: HYDRANT NE 58.8' (GONE)

TEL POLE NW 23.88' (GONE)

20" FRUIT TREE NW 86.6' (GONE)

W.P.A.-(1930'S) NW-31 IRON. T2S, R10E INDICATE SAME WITNESSES AS ABOVE LISTED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" STEEL BAR IN CONCRETE MONUMENT/MONUMENT BOX AT INKSTER RD & CARLYSLE .
(ASPHALT PAVEMENT)

M-11/M-10: WPA=2636.53'; MEAS=2637.18

M-11/M-12: WPA=2633.36'; MEAS=2633.32

M-10/M-11/M-12: WPA=180°29'40"; MEAS=180°29'27"

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-11: SECTION CORNER 25&36, T2S R9E, FOUND 1/2" STEEL BAR IN CONC MON/MON BOX. THE

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER. PLACED W.C.REMON. BRASS MARKER AND CAP "PPP PS 30096".

SET NAIL/WCR TAG IN NORTHWEST FACE UTILITY POLE N65°E 58.55'

CENTERLINE OF FIRE HYDRANT STEM N77°E 105.10'

SET NAIL/WCR TAG IN NORTHEAST FACE UTILITY POLE S57°E 64.55'

SET NAIL/WCR TAG IN SOUTHEAST FACE UTILITY POLE S40°W 78.95'

SET NAIL/WCR TAG IN NORTHEAST FACE UTILITY POLE N49°W 61.98'

*2-R
11-D-MISC*

Signed by *[Signature]*
Surveyor's Michigan License No. 30096

Date 22 DEC 94

RC 1472