

**SURVEY & REMONUMENTATION**

APR 05 1996

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

**LIBER 28469 PAGE 654**

WAYNE (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 2 S R 9 E M-12  
 T \_\_\_\_\_ R \_\_\_\_\_ CITY OF INKSTER  
 T \_\_\_\_\_ R \_\_\_\_\_ NANKIN TOWNSHIP  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-14-95 *[Signature]*

WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

95270183

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **PETER P. PALCZYNSKI** in a field survey on 13 DECEMBER, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1816 G.L.O. - SET POST BEECH 10" N31°E 15 LKS.  
 JOSEPH FLETCHER DO 9" S45°E 19 LKS.

\$ 10.00 DEED  
 18 DEC 95 3:01 P.M. RECEIPT# 75B  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI

SEE BACK OF THIS SHEET (NEXT PAGE) FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

\$ 4.00 REMONUMENTATION

FOUND 3/4" IRON PIPE IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF ANNAPOLIS RD. & INKSTER ROAD ASPHALT PAVEMENT.

MEASURED:  
 M-11/M-12/B-12 = 90°08'12"  
 B-12/M-12/M-13 = 89°29'35"  
 M-13/M-12/L-12 = 90°02'47"  
 L-12/M-12/M-11 = 90°19'28"

M-12 IN T2S, R9E, IS THE SAME CORNER AS A-12, T2S, R10E.



CORNER POSITION VERIFIED USING 1 WITNESS AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:  
 M-12 / M-11 = 2633.30'  
 M-12 / B-12 = 2651.19'  
 M-12 / M-13 = 2650.20'  
 M-12 / L-12 = 2641.66'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-12, T2S, R9E & A-12, T2S, R10E,  
 FOUND 3/4" IRON PIPE IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF ANNAPOLIS RD. & INKSTER ROAD ASPHALT PAVEMENT. SET 1/2" X 18" STEEL BAR IN PIPE WITH "WAYNE COUNTY REMON" GRAY CAP ON BAR.

SET NAIL/WCR TAG NORTHWEST FACE OF UTILITY POLE N47°E 50.65'  
 SOUTHWEST PORCH CORNER AT HOUSE # 4551 (1) N49°E 77.22'  
 FOUND CONCRETE MONUMENT N53°E 74.67'  
 CENTERLINE FIRE HYDRANT STEM S45°E 75.46'  
 SET NAIL/WCR TAG IN NORTHWEST FACE OF UTILITY POLE S39°E 60.91'  
 FOUND IRON PIPE S53°W 73.92'  
 SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE S55°W 61.78'  
 SET NAIL/WCR TAG IN NORTHEAST FACE OF UTILITY POLE N49°W 68.28'  
 CENTERLINE FIRE HYDRANT STEM N38°W 77.45'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 15 DEC 95

Surveyor's Michigan License No. 30096  
 2S9EM-12.DOC

4 P

**1995 WAYNE COUNTY REMONUMENTATION PROGRAM**

Continuation of Section "A"

History compiled by:  
Peter P. Palczynski, # 30096  
AMBIT LAND SURVEYORS, INC.

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST  
M-12 (E. 1/4 CORNER OF SECTION 36 & W. 1/4 CORNER OF SECTION 31, T2S, R10E, A-12)

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C. LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER W.P.A.			'SET POST	BEECH 10' DO 9'	N31°E 15 LKS. S45°E 19 LKS.		NOTES = 40.00 CHAINS
1930'S				IRON (E-36 #156 FOR NANKIN TOWNSHIP T2S, R9E)	S.W. PORCH CORNER 16" MAPLE STOP SIGN EDISON POLE	NE 77.22' SE 71.68' SW 65.89' NW 43.67'	1 2 3 4	M = 77.22' GONE GONE GONE
1937 OCTOBER	PATE & HIRN, ENGINEERS EDWIN H. PATE, P.E. "VAN BORN FARMS SUB" L.66, P. 14 W.C.R.	#695	S.E. 1/4 SECTION 36	IRON (W-31 # 144 FOR DEARBORN TOWNSHIP T2S, R10E)	S.W. PORCH CORNER 16" MAPLE 24" MAPLE FACE OF SIGN POST	NE 77.22' SE 57.20' SE 33.45' NW 33.52'	1 5 6 7	M = 77.22' GONE GONE GONE W.P.A. RECORD: M-12/M-11 = 2633.36' & 2633.13' M-12/B-12 = 2651.64' M-12/M-13 = 2650.15' & 2649.87' M-12/L-12 = 2641.86' M-11/M-12/B-12 = 90° 10' 30" B-12/M-12/M-13 = 89° 27' 50" M-13/M-12/L-12 = 90° 02' 10" L-12/M-12/M-11 = 90° 20' 30" PLAT RECORD M-12/L-12 = 2641.60' M-13/M-12/L-12 = 90° 02' 40'
1939 AUGUST	MASON L. BROWN & SON L.T. BROWN, R.L.S. "CHOICE OF INKSTER SUB" L. 67, P. 12 W.C.R.	#2967	N.E. 1/4 SECTION 36	NOT STATED	NO WITNESSES			PLAT RECORD: L-12/M-12M-11 = 90° 23' 10'
1965 JUNE	EDWIN H. PATE, R.L.S. "DEMBy TERRACES SUB." L.86, P. 29 & 30	#695	N.E. 1/4 SECTION 36	NOT STATED	NO WITNESSES			PLAT RECORD: L-12M-12M-11 = 90° 25' 00"

FILED DO NOT MAIL