

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

MAR 17 1998

For corners in

WAYNE
(County)

Located In: T 2S, R 10E

Corner Code # A-4 DEARBORN HTS.

SECTION

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-11-97 *DPJ*
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Public Land Survey	Common To:	T 2S R 9E	M-4
		T R	GARDEN CITY
		T R	NANKIN TOWNSHIP
		T R	
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, PETER P. PALCZYNSKI in a field survey on 1 DECEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST BEECH 10" N11°E 12 LKS.
JOSEPH FLETCHER DO 12" S20°E 20 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

\$10.00 DEED
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #42846

\$4.00 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MAPLEWOOD AVE. & INKSTER ROAD IN 50' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096" ON CONC. MON.

MEASURED:
M-3/M-4/M-5 = 180°02'33"
(WPA = 180°02'30"
180°02'15")
M-5/M-4/M-3 = 179°57'27"
(WPA = 179°57'45"
179°57'30")

M-4 IN T2S, R9E, IS THE SAME CORNER AS A-4, T2S, R10E.

CORNER POSITION VERIFIED USING COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
M-4 / M-5 = 2566.60' (2566.25'/2566.52' WPA)
M-4 / M-3 = 2700.27' (2700.37'/2700.40' WPA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4, T2S, R9E & A-6, T2S, R10E, FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MAPLEWOOD AVE. & INKSTER ROAD IN 50' WIDE ASPHALT PAVEMENT WITH CONCRETE CURBS. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096" ON CONC. MON.

SW CORNER BRICK WALL / SIGN
FOUND IRON PIPE
FOUND NAIL/WCRC REF PT IN SW FACE UTILITY POLE
CENTERLINE FIRE HYDRANT STEM
FOUND STEEL ENCASED CONCRETE MONUMENT
FOUND STEEL ENCASED CONCRETE MONUMENT
SET NAIL/WCR TAG IN NE FACE OF UTILITY POLE
FOUND STEEL ENCASED CONCRETE MONUMENT
CENTERLINE FIRE HYDRANT STEM

N55°E 72.95'
S53°E 74.67'
S44°E 51.29'
S43°E 61.60'
S55°W 73.21'
N61°W 91.25'
N53°W 60.92'
N43°W 87.73'
N21°W 127.38'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *PPJ* Date 11 DEC 97

Surveyor's Michigan License No. 30096
2S9EM-4.DOC

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											



1997 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

History compiled by:
 Peter P. Palczynski, P.S. # 30096
 AMBIT LAND SURVEYORS, INC.

M-4 (E. 1/4 CORNER OF SECTION 12 & W. 1/4 CORNER OF SECTION 7, T2S, R10E, A-4)
 NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER W.P.A.				SET POST	BEECH 10" DO 12"	N11°E 12 LKS S20°E 20 LKS.		NOTES = 40.00 CHAINS
1930'S					IRON (E-12 #52 FOR NANKIN TOWNSHIP T2S, R9E)	3" ELM CONC CULVERT TWIN APPLE	NE 48.2' SE 171.08' NW 34.45'	1 2 3	GONE GONE GONE
					IRON (W-7 # 40 FOR DEARBORN TOWNSHIP T2S, R10E)	3" ELM CONC CULVERT TWIN APPLE	NE 48.2' SE 171.08' NW 34.45'	1 2 3	GONE GONE GONE

W.P.A. RECORD:
 M-4/M-5 = 2566.25' / 2566.52'
 M-4/M-3 = 2700.37' / 2700.40'
 M-3/M-4/M-5 = 180° 02' 30" / 180° 02' 15"
 M-5/M-4/M-3 = 179° 57' 45" / 179° 57' 30"

SURVEY &
 REMONUMENTATION
 MAR 17 1998
 SECTION