

L129366PA903

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 10.00 DEED
30 DEC 96 1:39 P.M. RECEIPT# 45B
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI

For corners in

WAYNE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 2S R 9E

M-6

GARDEN CITY
NANKIN TOWNSHIP

T R

T 2S R 10E

Common Corner

T R

A-06 ✓

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

\$ 4.00 REMONUMENTATION

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-18-1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST B. ASH 10" N37°W 20 LKS.
JOSEPH FLETCHER W. ASH 9" S47°W 6 LKS.

SEE BACK OF THIS SHEET (NEXT PAGE)
FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MARQUETTE AVE. & INKSTER ROAD ASPHALT PAVEMENT. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096" ON CONC. MON.

MEASURED:
M-5/M-6/B-6 = 90°26'48"
B-6/M-6/M-7 = 89°44'30"
M-5/M-6/M-7 = 180°11'18"
M-7/M-6/M-5 = 179°48'42"

M-6 IN T2S, R9E, IS THE SAME CORNER AS A-6, T2S, R10E.

CORNER POSITION VERIFIED USING 2 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
M-6 / M-5 = 2640.37' (2640.01'/2640.14' WPA)
M-6 / M-7 = 2641.54' (2641.13'/2641.33' WPA)
M-6 / B-6 = 2642.43' (2642.28' WPA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6, T2S, R9E & A-6, T2S, R10E, FOUND 1/2" IRON IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE INTERSECTION OF MARQUETTE AVE. & INKSTER ROAD ASPHALT PAVEMENT. SET BRASS WAYNE COUNTY REMON WASHER & PLASTIC CAP "PPP PS #30096" ON CONC. MON.	CENTERLINE FIRE HYDRANT STEM (6) (R=94.51')	N21°E	94.51'
	FOUND IRON PIPE	N54°E	73.65'
	SET NAIL/WCR TAG IN SOUTHEAST FACE OF 18" OAK	N59°E	99.67'
	CENTERLINE FIRE HYDRANT STEM	N73°E	104.44'
	FOUND CONCRETE MONUMENT	S70°E	127.81'
	FOUND CONCRETE MONUMENT	S54°E	117.23'
	SET NAIL/WCR TAG IN WEST FACE OF UTILITY POLE (5) (R=63.57')	S48°E	63.57'
	CENTERLINE FIRE HYDRANT STEM	S17°W	156.34'
	SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE	N61°W	61.14'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by

[Signature]

Date

30 DEC 96

Surveyor's Michigan License No. 30096

2S9EM-6.DOC



4R
10D
[Signature]

1996 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

History compiled by:
Peter P. Palczynski, P.S. # 30096
AMBIT LAND SURVEYORS, INC.

M-6 (E. 1/4 CORNER OF SECTION 13 & W. 1/4 CORNER OF SECTION 18, T2S, R10E, A-6)

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER				SET POST	B. ASH 10" W. ASH 9"	N37°W 20 LKS S47°W 6 LKS.		NOTES = 40.00 CHAINS
1930'S	W.P.A.				IRON (E-13 #78 FOR NANKIN TOWNSHIP T2S, R9E)	36" ELM 40" OAK 8" ELM	NE 41.33' SE 31.55' NW 28.90'	1 2 3	GONE GONE GONE
3/22/72	MASON L. BROWN & SON, INC. WILLIAM G. CARLSON, PE, RLS SURVEY #S-31004-D & E	#14759	C.S. 134 C.S. 135	E. 1/2 SECTION 13	IRON (W-18 #66 FOR DEARBORN TOWNSHIP T2S, R10E)	36" ELM 40" OAK 8" ELM	NE 41.33' SE 31.55' NW 28.90'	1 2 3	GONE GONE GONE W.P.A. RECORD: M-6/M-5 = 2640.01 / 2640.14' M-6/M-7 = 2641.13' / 2641.33' M-6/B-6 = 2642.28' M-5/M-6/M-7 = 180° 11' 30" / 180° 11' 40" M-7/M-6/M-5 = 179° 48' 30" / 179° 48' 20" M-5/M-6/B-6 = 90° 27' 15" B-6/M-6/M-7 = 89° 44' 25"
3/22/72	MASON L. BROWN & SON, INC. WILLIAM G. CARLSON, PE, RLS	#14759	RC 45	E. 1/2 SECTION 13	FOUND IRON BAR IN MONUMENT BOX	NAIL MSHD IN DE POLE PK NAIL IN DE POLE CENTERLINE HYDRANT	N60°W 61.70' S48°E 63.60' N21°E 94.50'	4 5 6	GONE M = 63.57' M = 94.51'
3/30/92	LAND S.E.A. CORP. ERNEST F. BROSCHE, RLS SURVEY #G-8968-A & B	#12017	CS 2006 CS 2007	N.E. 1/4 SECTION 13	FOUND IRON BAR IN MONUMENT BOX FOUND MON IN MON BOX	NAIL MSHD IN DE POLE PK NAIL IN DE POLE CENTERLINE HYDRANT NO WITNESSES	N60°W 61.70' S48°E 63.60' N21°E 94.50'	4 5 6	GONE M = 63.57' M = 94.51'

LI29366PA904