

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

LI29358PA640

For corners in

WAYNE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 2S R 9E

M-8

T \_\_\_\_\_ R \_\_\_\_\_

INKSTER

T \_\_\_\_\_ R \_\_\_\_\_

NANKIN TOWNSHIP

T 2S R 10E

COMMON TO

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

A-08 ✓

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Compliance with  
 ACT 345, P.A. 1990

*DPJ*

APPROVED ON: DEC. 18, 1996  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1816 G.L.O. - SET POST      SUG 12'      N80°E 13 LKS.  
 JOSEPH FLETCHER      W.O. 20'      S62°W 25 LKS.

\$ 10.00 DEED  
 26 DEC 96 8:22 A.M.      RECEIPT# 18  
 RECORDED  
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI  
 \$ 4.00 REMONUMENTATION

SEE BACK OF THIS SHEET (NEXT PAGE)  
 FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" IRON IN MONUMENT BOX, AT CENTERLINE INTERSECTION OF AVONDALE AVE. & INKSTER ROAD ASPHALT PAVEMENT. SET GRAY "WAYNE COUNTY REMONUMENTATION" CAP ON 3/8" IRON.

MEASURED:  
 M-7/M-8/B-8 = 90°30'09"  
 B-8/M-8/M-9 = 89°48'22"  
 M-9/M-8/L-8 = 90°10'05"  
 L-8/M-8/M-7 = 89°31'24"

M-8 IN T2S, R9E, IS THE SAME CORNER AS A-8, T2S, R10E.



CORNER POSITION VERIFIED USING 2 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:  
 M-8 / M-7 = 2648.83' (R=2648.40/2648.44')  
 M-8 / B-8 = 2651.55' (R=2651.69')  
 M-8 / M-9 = 2647.48' (R=2647.26/2647.50')  
 M-8 / L-8 = 2667.69' (R=2665.84')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 T2S, R9E & A-8, T2S, R10E,	FOUND PK NAIL/WCRC REF PT WASHER IN SE FACE UTILITY POLE	N44°E	52.87'
FOUND 3/8" IRON IN MONUMENT BOX, AT CENTERLINE INTERSECTION OF AVONDALE AVE. & INKSTER ROAD ASPHALT PAVEMENT. SET GRAY "WAYNE COUNTY REMONUMENTATION" CAP ON 3/8" IRON.	CENTERLINE FIRE HYDRANT STEM	S76°E	123.86'
	FOUND PK NAIL/WCRC REF PT WASHER IN SW FACE UTILITY POLE	S39°E	61.15'
	SET NAIL/WCR TAG IN SOUTHWEST FACE OF UTILITY POLE	S73°W	57.97'
	CENTERLINE FIRE HYDRANT STEM	S50°W	50.76'
	FOUND CONCRETE MONUMENT	N59°W	70.48'
	FOUND PK NAIL/WCRC REF PT WASHER IN SW FACE UTILITY POLE	N58°W	51.85'

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *DPJ* Date 23 DEC 96

Surveyor's Michigan License No. 30098  
 2S9EM-8.DOC

Continuation of Section "A"

1996 WAYNE COUNTY REMONUMENTATION PROGRAM

History compiled by:  
Peter P. Palczynski, P.S. # 30096  
AMBIT LAND SURVEYORS, INC.

M-8 (E. 1/4 CORNER OF SECTION 24 & W. 1/4 CORNER OF SECTION 19, T2S, R10E, A-8)

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST

COMPANY  
SURVEYOR  
JOB #

G.L.O.  
JOSEPH FLETCHER  
W.P.A.

DATE

P.A. 74  
L.C.R.C.

MONUMENT  
DESCRIPTION

WITNESSES

BEARING  
& DISTANCE

ID #

COMMENT

1816

SET POST

SUG. 12"  
W.O. 20"

N80°E 13 LKS  
S62°W 25 LKS.

NOTES = 40.00 CHAINS

1930'S

IRON  
(E-24#104 FOR  
NANKIN TOWNSHIP  
T2S, R9E)

CROSS ON SIGN POST  
ED GUY POLE  
BASE OF FIRE HYD  
ED POLE

NE 34.65'  
SE 62.32'  
SW 66.90'  
NW 54.08'

1 GONE  
2 GONE  
3 GONE  
4 GONE

2/22/73

IRON  
(W-19 # 92 FOR  
DEARBORN TOWNSHIP  
T2S, R10E)

CROSS ON SIGN POST  
ED GUY POLE  
BASE OF FIRE HYD  
ED POLE

NE 34.65'  
SE 62.32'  
SW 66.90'  
NW 54.08'

1 GONE  
2 GONE  
3 GONE  
4 GONE

W.P.A. RECORD:  
M-8/M-7 = 2648.40 / 2648.44'  
M-8/M-9 = 2647.26' / 2647.50'  
M-8/B-8 = 2651.69'  
M-8/L-8 = 2665.84'  
M-7/M- 8/B-8 = 90° 27' 10"  
B-8/M- 8/M-9 = 89° 51' 20"  
M-9/M-8/L-8 = 90° 11' 10"  
L-8/M-8/M-7 = 89° 30' 00"

2/22/73

WARNER, CANTRELL &  
PADMOS, INC.  
TERENCE B. CANTRELL  
RLS

N.E. 1/4 SECTION 24

FOUND 3/4" IRON PIPE

NOT LEGIBLE

C.S. 768  
C.S. 766

#5782

LI29358PA641