

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L129358PA634

For corners in

WAYNE
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------------------|
| 1. Public Land Survey | T <u>2S</u> R <u>9E</u> | <u>M-10</u> |
| | T _____ R _____ | <u>INKSTER</u> |
| | T _____ R _____ | <u>NANKIN TOWNSHIP</u> |
| | T <u>2S</u> R <u>10E</u> | <u>Common TO</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>A-10</u> |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Compliance with
ACT 345, P.A. 1990

APPROVED ON: DEC 18, 1996
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, PETER P. PALCZYNSKI in a field survey on 13 DECEMBER, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1816 G.L.O. - SET POST B.O. 12" N42°W 36 LKS.
 JOSEPH FLETCHER DO. 10" S71°W 27 LKS.

\$ 10.00 DEED
 26 DEC 96 8:22 A.M. RECEIPT# 1B
 RECORDED
 FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION

SEE BACK OF THIS SHEET (NEXT PAGE)
 FOR CONTINUATION OF SECTION "A"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF INKSTER ROAD ASPHALT PAVEMENT. SET 3/8" STEEL BAR WITH GRAY "WAYNE COUNTY REMONUMENTATION" CAP ON 3/8" STEEL BAR.

MEASURED:
 M-9/M-10/M-11 = 180°01'19"
 M-11/M-10-M-9 = 179°58'41"

M-10 IN T2S, R9E, IS THE SAME CORNER AS A-10, T2S, R10E.

CORNER POSITION VERIFIED USING 2 WITNESSES AND COMPARISONS TO RECORD INFORMATION FROM SECTION "A".

MEASURED:
 M-10/ M-9 = 2633.85' (R=2634.26/2634.23)
 M-10/ M-11 = 2637.18' (R=2636.19/2636.53)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 T2S, R9E & A-10, T2S, R10E, FOUND 3/4" IRON PIPE IN CONCRETE MONUMENT / MONUMENT BOX, AT CENTERLINE OF INKSTER ROAD ASPHALT PAVEMENT. SET 3/8" STEEL BAR WITH GRAY "WAYNE COUNTY REMONUMENTATION" CAP ON 3/8" STEEL BAR.	FOUND NAILWASHER RLS #14759 IN NW FACE OF UTILITY POLE SET NAILWCR TAG IN NORTHWEST FACE OF SAME UTILITY POLE NORTHWEST CORNER OF CATCH BASIN RIM SET NAILWCR TAG IN SOUTHWEST FACE OF UTILITY POLE SET NAILWCR TAG IN SOUTHWEST FACE OF UTILITY POLE SET NAILWCR TAG IN SOUTHWEST FACE OF UTILITY POLE SET NAILWCR TAG IN SOUTHWEST FACE OF UTILITY POLE SET NAILWCR TAG IN SOUTHWEST FACE OF UTILITY POLE SET NAILWCR TAG IN SOUTHWEST FACE OF UTILITY POLE	N29°E 61.06' N29°E 61.08' S27°E 43.25' S09°E 188.12' S25°W 69.33' N09°W 177.33'
--	---	--

SELECTED LOCATION IS ACCEPTED BY THE CONTRACTOR AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Date 23 DEC 96

Surveyor's Michigan License No. 30096

2S9EM-10DOC

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



1996 WAYNE COUNTY REMONUMENTATION PROGRAM

Continuation of Section "A"

NANKIN TOWNSHIP TOWN 2 SOUTH, RANGE 9 EAST

M-10 (E. 1/4 CORNER OF SECTION 25 & W. 1/4 CORNER OF SECTION 30, T2S, R10E, A-10)

History compiled by:

Peter P. Palczynski, P.S. # 30096

AMBIT LAND SURVEYORS, INC.

DATE	COMPANY SURVEYOR JOB #	P.S. #	P.A. 74 L.C.R.C.	LOCATION OF SURVEY	MONUMENT DESCRIPTION	WITNESSES	BEARING & DISTANCE	ID #	COMMENT
1816	G.L.O. JOSEPH FLETCHER				SET POST	B.O. 12'	N42°W 36 LKS		NOTES = 40.00 CHAINS
1930'S	W.P.A.				IRON (E-25 #130 FOR NANKIN TOWNSHIP T2S, R9E)	DO. 10' 48" MAPLE 24" MAPLE LIGHT POLE	S71°W 27 LKS. NE 22.04' SE 33.42' SW 28.70'	1 2 3	GONE GONE GONE
					IRON (W-30 # 118 FOR DEARBORN TOWNSHIP T2S, R10E)	48" MAPLE 24" MAPLE LIGHT POLE	NE 22.04' SE 33.42' SW 28.70'	1 2 3	GONE GONE GONE

W.P.A. RECORD:
M-10/M-9 = 2634.26 / 2634.23
M-10/M-11 = 2636.19 / 2636.53
M-9/M-10/M-11 = 179°59'15"
M-11/M-10/M-9 = 180°00'00"

LI29358PA635