

City of Inkster

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne

(County)

Located in:

Corner Code #

1. Public Land Survey

T2S R 10E

B-9

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-10-97
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, LAWRENCE R. FEINDT, in a field survey on DECEMBER 4, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

44.00 REMONUMENTATION
RECORDED
FOREST E. YOUNGBLOOD, REGISTER OF DEEDS
WAYNE COUNTY, MI
Receipt #42845

47.00 GLED

A. Description of original monument and accessories and/or subsequent restoration:
B-9) 1/4 Corner Common to Sections 19 and 30, T 2 S, R 10 E
GENERAL LAND OFFICE WAYNE COUNTY BUREAU OF TAXATION
SET POST FOR CORNER IRON
SUGAR 10°-360°E-9 LINKS(5.94') NE'LY-59.00-SIGN POST (GONE)
SUGAR 12°-N47°E-12 LINKS(7.92') SE'LY-28.03'-TREE (GONE)
DECEMBER 21, 1816 SW'LY-108.25-EDISON POLE (GONE)
BY: JOSEPH FLETCHER, DS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-9) 1/4 Corner Common to Sections 19 and 30, T 2 S, R 10 E
No direct evidence of corner was found. Corner was re-established from property irons found in "Westwood Hills Subd'n." as recorded in Liber 54, Page 61.
Distance to C-9 measured 2668.69' (WPA=2668.70')

SURVEY &
REMONUMENTATION

MAR 17 1998

SECTION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-9) 1/4 Corner Common to Sections 19 and 30, T 2 S, R 10 E

Set concrete monument with Wayne County brass disk stamped with license #21566 in monument box at computed corner location in the center line of Westwood Drive. Road surface is concrete. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Witnesses: N15°W - 105.18'- Found PK nail in NE side of utility pole
N50°E - 42.57'-Set nail and Wayne county brass disk stamped with license #21566 in NW side of 26" Maple
S70°E - 28.93'-Set nail and WCR tag in NE side of 12" Elm
N75°W- 54.35'-NE corner of house foundation (26613 West Hills Drive)

Signed by Lawrence R. Feindt
Surveyor's Michigan License No. 21566

Date December 9, 1997