

**SURVEY &  
REMONUMENTATION**

LIBER **28451** PAGE **025**

City of Inkster **APR 05 1996**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne  
(County)

**COMMISSION**

Located In:

Corner Code ##

- |                                       |                          |             |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey                 | T <u>2S</u> R <u>10E</u> | <u>B-11</u> |
|                                       | T _____ R _____          | _____       |
|                                       | T _____ R _____          | _____       |
|                                       | T _____ R _____          | _____       |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |
| 4. Lot No. _____, Recorded Plat _____ |                          |             |
| 5. Private Claims _____               |                          |             |

Compliance with  
ACT 345, P.A. 1990  
APPROVED ON: 12-6-95  
WAYNE COUNTY REMONUMENTATION  
P&R GROUP COMMITTEE  
**Register of Deeds Stamp & File Number**

95262304

I, Lawrence R. Feindt, in a field survey on November 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-11) 1/4 Corner common to Sections 30 and 31, T 2 S, R 10 E  
 GENERAL LAND OFFICE                      WAYNE COUNTY BUREAU OF TAXATION  
 SET POST FOR CORNER                      IRON  
 BEECH 12"-N69°E-17 LINKS(11.22')      NE'LY-37.94'-MAPLE  
 W. WALNUT 12"-S10°W-38 LINKS(25.08')   SE'LY-60.65'-LIGHT POLE  
 DECEMBER 21, 1816                          WNW'LY-35.40'-MANHOLE  
 BY: JOSEPH FLETCHER, DS                    NW'LY-61.80'-TREE

\$ 7.00 DEED  
\$ 4.00 REMONUMENTATION  
\$ 4.00 REMONUMENTATION  
8 DEC 95 9:43 A.M. RECEIPT# 68  
FOREST E. YORRISON, REGISTER OF DEEDS  
MICHIGAN COUNTY, MI

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-11) 1/4 Corner common to Sections 30 and 31, T 2 S, R 10 E  
 No direct evidence of corner was found. Corner was reestablished from WPA notes. Distance to A-11 measured 2641.28' (WPA = 2641.35'). Distance to C-11 measured 2645.65' (WPA = 2645.72'). Distance to B-12 measured 2642.02' (WPA = 2642.02'). Corner was confirmed with irons found in "Rob't. M. Grindley's Sub. No. 10 of Little Farms" as recorded in Liber 39, Page 70; "West-woods Subdivision" as recorded in Liber 40, Page 30; and "Greater Dearborn Sub." as recorded in Liber 55, Page 62. Found one remaining witness from WPA. A discrepancy was noted with local irons near the intersection of Carlisle Avenue and John Daly Road of 5'± east and west.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-11) 1/4 Corner common to Sections 30 and 31, T 2 S, R 10 E  
 Set concrete monument with brass disk stamped #21566 in monument box at the intersection of Carlisle Road and John Daly Road. Road surface is concrete. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.  
 Witnesses: S31°W - 62.23' - Set nail in northwest face of utility pole and affixed Wayne County brass disk stamped with license #21566  
 S27°E - 60.56' - Set nail and WCR tag in east face of guy anchor pole  
 N70°E - 76.76' - Top bolt of fire hydrant  
 N50°W - 84.08' - Southeast corner of brick house #3656  
 N59°W - 35.77' - Center of manhole (old WPA witness)

4R  
7D  
DPJ

Signed by Lawrence R. Feindt Date December 7, 1995  
 Surveyor's Michigan License No. 21566