

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 25992 PA 830

For corners in

COMMISSION

<u>Wayne</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 11-30-93 DPJ
 WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		⊙										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Lawrence R. Feindt, in a field survey on October 25, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-3) Corner Common to Sections 5, 6, 7 & 8, T 2 S, R 10 E
 GENERAL LAND OFFICE SET POST FOR CORNER BEECH 12"-324 W-9 LINKS(5.94') BEECH 12"-N89 E-40 LINKS(26.40') DECEMBER 22, 1816 BY: JOSEPH FLETCHER, DS
 WAYNE COUNTY BUREAU OF TAXATION CROSS SE'LY-66.22'-SUB. COR. SW'LY-84.50'-IRON NW'LY-69.45'-30" ELM

93 NOV 30 AM 11:17
 FOREST E. YOUNGBLOOD
 REGISTER OF DEEDS
 WAYNE COUNTY, MI

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3) Corner Common to Sections 5, 6, 7 & 8, T 2 S, R 10 E
 Found 1/2" iron rod in monument box 12"± deep. Distance to B-3 measured 2624.71' (WPA = 2624.98'). Corner was confirmed with irons found in "Valley View Subdivision" as recorded in Liber 74 of Plats, Page 70; "Annis Hawthorne Manor Sub." as recorded in Liber 54 of Plats, Page 61, Wayne County records; and "Frischkorn's Golfdale Quarter Acres Subdivision" as recorded in Liber 48, Page 14, Wayne County records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3) Corner Common to Sections 5, 6, 7 & 8, T 2 S, R 10 E
 Found 1/2" iron rod in monument box 12"± deep, and is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N62°W - 83.06' - SE bolt of steel light pole #S40DD389
 N39°E - 77.95' - Found PK nail with WCRC disk in SE face of utility pole
 S57°E - 65.09' - Found PK nail with WCRC disk in SW face of utility pole
 S41°W - 63.80' - Found PK nail with WCRC disk in SE face of utility pole and affixed Wayne County brass disk stamped with licence #21566.

2R
11K

Signed by Lawrence R. Feindt Date November 29, 1993
 Surveyor's Michigan License No. 21566