

FEB 28 2000

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

CITY OF DEARBORN HEIGHTS  
or corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>C-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber-30855 Page-2  
99593134 12/29/1999  
F.E. Younblood, Wayne Co. Register of Deeds

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-9-99  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

LAWRENCE R. FEINDT, in a field survey on December 2, 1999  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
**C-5 CORNER COMMON TO SECTIONS 7, 8, 17 & 18 T2S-R10E**

GENERAL LAND OFFICE	WAYNE COUNTY BUREAU OF TAXATION	MICH DEPT OF TRANSPORTATION
Set Sec. corner	Cross	Nov. 8, 1977 By: Ervin P. Miller
B. Ash 12" S30°E 12 Lks (7.92')	NE'ly - 84.15' - Iron (FOUND)	Mushroom Head Iron in monument box
Elm 30" N74°W 22 Lks (14.52')	SE'ly - 13.05' - X in MH Ring (GONE)	N50°E - 70.92' - Traffic/light pole (FOUND)
December 21, 1816	SW'ly - 31.95' - Tel. Pole (GONE)	S35°E - 72.03' - Traffic/light pole (FOUND)
By: Joseph Fletcher	NW'ly - 83.75' - Fire Hydrant (FOUND)	S45°W - 71.70' - Traffic/light pole (FOUND)
		N40°W - 76.61' - Traffic/light pole (FOUND)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**C-5 CORNER COMMON TO SECTIONS 7, 8, 17 & 18 T2S-R10E**

Found 1 1/2" rod in monument box in the center line of Ford Road and Beech-Daly Road. Corner was confirmed with irons found in "CUMMINGS FORD ROAD SUB'M" as recorded in Liber 53 Page 79 "CONLEY'S FORD-GULLEY SUBDIVISION" as recorded in Liber 55 Page 50; comparisons to WPA surveys conducted in the 1930's and six previous witnesses found.

Distance to corner D-5 Measured 2646.94' (WPA = 2646.90' PLAT = 2647.56')  
Distance to corner B-5 Measured 2640.13' (WPA = 2640.04' PLAT = 2640.00')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**C-5 CORNER COMMON TO SECTIONS 7, 8, 17 & 18 T2S-R10E**

Found 1 1/2" rod in monument box in concrete pavement at the intersection of Ford Road and Beech-Daly Road. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

- WITNESSES:**
- N44°E 70.90' Found nail & MSHD tag in SE side of utility pole (R=70.92')
  - N45°E 84.01' Found 3/4" iron pipe (R=84.15')
  - S39°E 72.00' Found nail & MSHD tag in NE side utility pole (R=72.03')
  - S42°W 71.69' Found nail & MSHD tag in SE side utility pole (R=71.70')
  - Set Wayne County Remon disk above MSHD tag.
  - N44°W 76.58' Found nail & MSHD tag in NE side utility pole (R=76.61')
  - N39°W 83.87' Top of fire hydrant (R=83.75')



Signed by Lawrence R. Feindt Date December 9, 1999

Surveyor's Michigan License No. 21566

R LCR 9 4R 1P A [Signature]