

FEB 28 1994

RC 1147

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 26992 PA 831

For corners in

Wayne (County) Located In: Corner Code #

1. Public Land Survey T 2S R 10E C-6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-93 *DRJ*
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Lawrence R. Feindt

I, Lawrence R. Feindt, in a field survey on October 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6) 1/4 Corner Common to Sections 17 and 18, T 2 S, R 10 E

GENERAL LAND OFFICE
 SET POST FOR CORNER
 W. ASH 9"-N64 W-17 LINKS(11.22')
 ELM 10"-N19 W-10 LINKS(6.60')
 DECEMBER 21, 1816
 BY: JOSEPH FLETCHER, DS

WAYNE COUNTY BUREAU OF TAXATION
 STONE
 NE'LY- 2.00'-POST
 SE'LY-10.40'-8" TWIN ASH
 S'LY -25.20'-6" TWIN ASH
 N'LY -56.50'-18" OAK

WAYNE COUNTY ROAD COMMISSION
 MON. IN BOX
 SE'LY-99.97'-MON.
 NW'LY-83.25'-TOP HYDRANT

FOUND CONCRETE MONUMENT IN HANDHOLE
 N40°E- 63.39'-PK NAIL IN SE SIDE P. POLE
 S50°E- 58.15'-PK NAIL IN SW SIDE P. POLE
 S30°W- 61.80'-PK NAIL IN SE SIDE P. POLE
 N50°W- 66.17'-PK NAIL IN SW SIDE P. POLE
 BY: KENNETH S. WILKERSON, PS #21584
 MARCH 19, 1980
 RECORDED IN LIBER 20851, PAGE 345, WCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6) 1/4 Corner Common to Sections 17 and 18, T 2 S, R 10 E

Found concrete monument in monument box at the intersection of Beech-Daly Road and Wilson Avenue. Distance to C-7 measured 2650.41' (WPA = 2649.39'). Corner was confirmed with irons found in "Conley's Ford-Gulley Subdivision" as recorded in Liber 55 of Plats, Page 50, Wayne County records; "Dearborn Oaks Sub'n. No. 3" as recorded in Liber 90, Page 44, Wayne County records; "Dearborn Oaks Sub'n. No. 4" as recorded in Liber 93, Pages 3 and 4, Wayne County records; and in "Cherry Hill Subdivision" as recorded in Liber 99, Pages 99 and 100, Wayne County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6) 1/4 Corner Common to Sections 17 and 18, T 2 S, R 10 E

Found concrete monument in monument box at the intersection of Beech-Daly Road and Wilson Avenue, and is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N38°E - 63.28' - Found PK nail in SE face of utility pole
 S51°E - 58.44' - Found PK nail in SW face of utility pole and affixed Wayne County brass disk stamped with license #21566
 S34°W - 61.79' - Found PK nail in SE face of utility pole
 N45°W - 66.08' - Found PK nail in SW face of utility pole



93 NOV 30 AM 11:17
 REGISTERED LAND SURVEYOR
 KENNETH S. WILKERSON
 PS #21584
 2R
 HKD

Signed by Lawrence R. Feindt Date November 29, 1993

Surveyor's Michigan License No. 21566