

FEB 28 1994

RC 1151

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 26992 PA 835

For corners in

<u>Wayne</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-93
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	⊙											
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Lawrence R. Feindt

I, Lawrence R. Feindt, in a field survey on October 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7) Corner Common to Sections 17, 18, 19 & 20, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER BEECH 10"-S32 W-13 LINKS (8.58') B. O. 16"-S45 E-48 LINKS (31.68') DECEMBER 21, 1816 BY: JOSEPH FLETCHER, DS WAYNE COUNTY ROAD COMMISSION NON. SE'LY-77.75'-8" POPLAR SW'LY-40.78'-12" ELM NW'LY-68.92'-14" ELM	WAYNE COUNTY BUREAU OF TAXATION (IRON) NNW'LY-34.33'-24" MAPLE SW'LY -76.40'-12" WALNUT NW'LY -97.55'-26" WILD CHERRY FOUND MONUMENT (MARCH 14, 1978) N45 32'E-72.19'-NAIL IN DE POLE S60 54'E 75.49'-NAIL IN DE POLE S52 W -66.23'-NAIL IN DE POLE N45 30'W-72.55'-NAIL IN DE POLE BY: PHILIP S. ENSMINGER, PS #21268 RECORDED IN LIBER 20053, PAGE 289, WCR	FOUND MONUMENT IN MONUMENT BOX N44 50'E-72.10'-NAIL S. SIDE OF L. POLE S61 16'E-75.85'-PK NAIL S. SIDE OF LIGHT POLE S51 17'W-66.67'-PK NAIL IN NW SIDE OF DETROIT EDISON POLE N16 45'W-43.49'-NAIL SE SIDE OF DETROIT EDISON POLE JULY 7, 1986 BY: WALTER JOHN ZBIKOWSKI, PS #21586 RECORDED IN LIBER 22834, PAGE 745, WCR
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7) Corner Common to Sections 17, 18, 19 & 20, T 2 S, R 10 E

Found concrete monument in monument box at the intersection of Beech-Daly Road and Cherry Hill Road. Distance to B-7 measured 2654.88' (WPA = 2654.96'), and distance to C-6 measured 2650.41' (WPA = 2649.39'). Corner was confirmed with irons found in "Gregory Meadows Subdivision" as recorded in Liber 67 of Plats, Page 8, Wayne County records; "Brand Acres Subdivision" as recorded in Liber 69 of Plats, Page 26, Wayne County records; and "Dearborn Oaks Sub'n." as recorded in Liber 86 of Plats, Pages 61-62, Wayne County records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7) Corner Common to Sections 17, 18, 19 & 20, T 2 S, R 10 E

Found concrete monument in monument box at the intersection of Cherry Hill Road and Beech-Daly Road, and is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses:

- N46°E - 72.14' - Found double-headed nail in SE face of utility pole
- S61°E - 75.47' - Found PK nail in NE face of utility pole
- S53°W - 66.07' - Found double-headed nail in NW face of utility pole
- S53°W - 66.54' - Found PK nail in NW face of utility pole and affixed Wayne County brass disk stamped with license #21566
- N45°W - 72.72' - Found double-headed nail in SW face of utility pole

Signed by Lawrence R. Feindt Date November 29, 1993

Surveyor's Michigan License No. 21566

93 NOV 30 AM 11:51
REGISTERED LAND SURVEYOR
WAYNE COUNTY, MI