

SURVEY & MONUMENTATION

\$ 4.00 REMONUMENTATION
 8 DEC 95 9:43 A.M. RECEIVED
 FOREST E. VOORHEES, REGISTER OF DEEDS
 1000 S. WOODRIDGE, MI

City of Dearborn Heights
 APR 05 1996 **LAND CORNER RECORDATION CERTIFICATE**
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Wayne (County) Located In: Corner Code #

1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>C-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

\$ 7.00 DEED

LIBER 28451 PAGE 027

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-6-95 *DRJ*

WAYNE COUNTY REMONUMENTATION FOUR CORNER COMMITTEE

Register of Deeds Stamp & File Number **6**

92262306

Lawrence R. Feindt, in a field survey on November 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13) South Corner Common to Sections 31 & 32, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER IRONWOOD 10"-N48 W-16 LINKS(10.56') BLACK OAK 12"-N04 E-33 LINKS(21.78') DECEMBER 16, 1816 BY: JOSEPH FLETCHER, DS	WAYNE COUNTY BUREAU OF TAXATION IRON NNE'LY-125.46'-15"MAPLE SSE'LY- 64.95'-MONUMENT SW'LY - 60.15'-CROSS E. COR. SIGN POST NW'LY - 55.71'-TELEPHONE POLE
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13) South Corner Common to Sections 31 & 32, T 2 S, R 10 E
 Found 1/2" pipe in monument box. Distance to D-13 measured 2626.27' (WPA = 2626.25'). Distance to B-13 measured 2630.36' (WPA = 2630.39'). Corner was confirmed with irons found in "Rougelvania Subdivision No. 1" as recorded in Liber 55 of Plats, Page 33. Monument also has been used as the corner common to Sections 5 & 6, T 3 S, R 10 E (C-1) as documented by local plats and the WPA notes. GLO notes indicate the corner common to Sections 5 & 6 to be 20 links (13.2') west of the corner common to Sections 31 & 32. No evidence of C-1 of T 3 S, R 10 E was found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13) South Corner Common to Sections 31 & 32, T 2 S, R 10 E
 Found 1/2" pipe in monument box at the intersection of Beech Daly Road and Van Born Road, and placed Wayne County brass disk stamped with license #21566 over pipe. Road surface is asphalt over concrete. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: S43°E - 85.48' - Northwest corner of building #25757
 S56°W - 73.82' - Set chiseled "X" in top center of fire hydrant
 N46°W - 62.48' - Set nail & #21566 cap in SW face of utility pole
 N57°E - 87.23' - Set chiseled "X" in top center of fire hydrant

Signed by Lawrence R. Feindt Date December 7, 1995

Surveyor's Michigan License No. 21566

4R
7D
DRJ