

FEB 28 2000

FILE DO NOT MAIL

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CITY OF DEARBORN
or corners in

<u>WAYNE</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
1. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber-30855 Page-3
99593151 12/29/1999
F.E. Youngblood, Wayne Co. Register of Deeds

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-9-99
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LAWRENCE R. FEINDT, in a field survey on December 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5				●									
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5 CORNER COMMON TO SECTIONS 8 & 17, T2S-R10E	GENERAL LAND OFFICE	WAYNE COUNTY BUREAU OF TAXATION	MICH DEPT OF TRANSPORTATION
	Set 1/4 Sec. corner	Mon	March 18, 1964 By: J. Klauza
	Beech 10" S73°E 18 Lks (11.88')	NE'ly - 38.30' - 8" Walnut(GONE)	Brass disk in monument box
	Ironwood 6" N69°E 4 Lks (2.64')	SE'ly - 72.00' - Fire Hydrant (FOUND)	S30°E - 72.25' - Guy Pole (GONE)
	December 23, 1816	SW'ly - 53.95' - Tel. Pole(GONE)	S40°W - 78.59' - Bldg Corner (FOUND)
	By: Joseph Fletcher	NW'ly - 70.32' - Fire Hydrant (FOUND)	N45°W - 74.95' - Power Pole (GONE)
			S40°E - 72.00' - Fire Hydrant(FOUND)
			N30°W - 70.30' - Fire Hydrant (FOUND)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 CORNER COMMON TO SECTIONS 8 & 17, T2S-R10E
Found 1/2" rod in monument box in the center line of Ford Road and Silvery Lane. Corner was confirmed with irons found in "SWEETS FORD-DEARBORN SUB'N No. 1" as recorded in Liber 55 Page 54; "COMEFORD'S FORD ROAD SUB'N" as recorded in Liber 51 Page 78; comparisons to WPA surveys conducted in the 1930's and three previous witnesses found.

Distance to corner E-5 Measured 2647.25' (WPA = 2647.13' PLAT = 2647.80')
Distance to corner C-5 Measured 2646.94' (WPA = 2646.90' PLAT = 2647.56')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 CORNER COMMON TO SECTIONS 8 & 17, T2S-R10E
Found 1/2" rod in monument box in concrete pavement at the intersection of Ford Road and Silvery Lane. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

- WITNESSES:
- N26°E 63.52' Found PK nail in West side of utility pole
 - S44°E 71.92' Top of fire hydrant (R=72.00')
 - S37°W 78.61' Found NE cor of brick bldg #25001 (R=78.59)
 - S27°W 67.24' Found PK nail in SE side utility pole. Set Wayne County Remon disk above old PK nail.
 - N29°W 70.30' Top of fire hydrant (R=70.30')



Signed by Lawrence R. Feindt Date December 9, 1999

Surveyor's Michigan License No. 21566

R LCR 9 4R 1 Pg A [Signature]