

FILE DO NOT MAIL

City of Dearborn

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

For corners in

Wayne

(County)

Located In:

Corner Code #

- |                                       |       |                   |            |
|---------------------------------------|-------|-------------------|------------|
| 1. Public Land Survey                 |       | <u>T 2S R 10E</u> | <u>D-9</u> |
|                                       |       | T ___ R ___       | _____      |
|                                       |       | T ___ R ___       | _____      |
|                                       |       | T ___ R ___       | _____      |
| 2. Property Controlling<br>in Section | S ___ | T ___ R ___       | _____      |
|                                       | S ___ | T ___ R ___       | _____      |
| 3. Miscellaneous<br>Property in Sec.  | S ___ | T ___ R ___       | _____      |
|                                       | S ___ | T ___ R ___       | _____      |

MAR 17 1998

SECTION

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-10-97 *DF*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, LAWRENCE R. FEINDT, in a field survey on DECEMBER 4, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
D-9) 1/4 Corner Common to Sections 20 and 29, T 2 S, R 10 E

GENERAL LAND OFFICE	MICHIGAN STATE HIGHWAY DEPARTMENT
SET POST FOR CORNER	3/8" PIPE
BEECH 10°-N54°E-25 LINKS(16.50')	N35°W-42.94'-N & C IN POWER POLE (GONE)
BEECH 20°-S58°E-48 LINKS(31.68')	S38°W-49.58'-N & C IN LIGHT POLE (FOUND)
DECEMBER 22, 1816	N65°E-103.06'-N & C IN LIGHT POLE (GONE)
BY: JOSEPH FLETCHER, DS	S18°E-84.00'-DRILL HOLE IN CHISELED SQUARE (GONE)
	FEBRUARY 19, 1964
	BY: BERNARD SWIEBODA, SURVEY CHIEF

\$7.00 DEED

RECORDED

FOREST E. YOUNGBLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI

Receipt #42845

\$4.00 REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9) 1/4 Corner Common to Sections 20 and 29, T 2 S, R 10 E

No direct evidence of corner was found. Only one Michigan State Highway Department remains. Corner was reestablished from property corner irons in "Georgia Park Subdivision No. 3" as recorded in Liber 65, Page 6 and "Westwood Dearborn Subdivision" as recorded in Liber 81, Page 45. Distance to C-9 measured 2600.49' and distance to E-9 measured 2618.84'.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9) 1/4 Corner Common to Sections 20 and 29, T 2 S, R 10 E

Set concrete monument and Wayne County brass disk stamped with license #21566 in monument box at the computed corner location in the center line of Westwood Avenue. Road surface is concrete. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Witnesses: S35°W - 49.49' - Found MSHD nail and tag in SE side of light pole (record=49.58')  
N65°W - 51.14' - "X" cut in top bolt of fire hydrant  
N60°E - 82.79' - SW anchor bolt of light pole #M40DA745  
S60°E - 56.40' - SW corner of stuccoed motel (Mc Inn)

Signed by Lawrence R. Feindt  
Surveyor's Michigan License No. 21566

Date December 9, 1997

R-LCR-7-4R-1P6-11 *DF*