

MAR 02 1999

DEC 22 1998  
FILE DO NOT MAIL

Liber-30032

Page-11

98455376ES

12/22/1998

68:318MC

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

CITY OF DEARBORN  
For corners in

WAYNE (County)	Located In:	Corner Code #
1. Public Land Survey	T 2S R 10E	D-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED  
FOREST E. YOUNGLOOD, REGISTER OF DEEDS  
WAYNE COUNTY, MI  
Receipt #101463

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-16-98  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4			3		2		1
3													
4	7			8		9			10		11		12
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, LAWRENCE R. FEINDT, in a field survey on December 9, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11 CORNER COMMON TO SECTIONS 29 & 32, T2S-R10E

GENERAL LAND OFFICE	WAYNE COUNTY BUREAU OF TAXATION	LCRC Liber 22479 Page 908
Set 1/4 Sec. corner	Iron	Oct 16, 1984 By: John Emig PS #10059
W. Oak 12" S45°W 3.27 Ch (215.82)	NE'ly - 59.57' - Corner sidewalk (GONE)	PK nail in concrete pavement
B. Oak 16" S32°E 3.43 Ch (226.38)	SW'ly - 46.73 - Stake (GONE)	N45°W - 39.70' - Nail in asphalt (GONE)
December 22, 1816	NW'ly - 54.40' - Pipe (GONE)	N66°E - 57.85' - Top bolt on hydrant (FOUND)
By: Joseph Fletcher		S41°E - 35.92' - Nail in utility pole (FOUND)
		Westerly - 33.00' - Iron (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 CORNER COMMON TO SECTIONS 29 & 32, T2S-R10E

Found PK nail in concrete joint in the center line of Carlisle Avenue and Westwood Avenue. Corner was confirmed with irons found in "DEARBORN GARDENS SUBDIVISION" as recorded in Liber 39 Page 40; "DEARBORN-TELEGRAPH SUBDIVISION" as recorded in Liber Page 19; by comparisons to WPA surveys conducted in the 1930's; and by two found witnesses from John Emig LCRC.

Distance to corner E-11 Measured 2629.57' (WPA = 2629.58')  
Distance to corner C-11 Measured 2599.82' (WPA = 2600.13')  
Distance to corner D-12 Measured 2635.92' (WPA = 2636.04')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 CORNER COMMON TO SECTIONS 29 & 32, T2S-R10E

Set concrete monument in monument box in concrete pavement at the intersection of Carlisle Avenue and Westwood Avenue. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

WITNESSES: N61°E - 57.84' - Center of top bolt of fire hydrant (R=57.85')  
S46°E - 36.00' - Found nail in NE side utility pole (NO ID) (R=35.92')  
S44°E - 36.05' - Set nail & WCR tag in the SW side of utility pole  
S41°W - 85.04' - Iron fence post at corner of iron fence  
N70°W - 44.77' - Set chiseled "X" in SE corner of catch basin

Signed by Lawrence R. Feindt Date December 16, 1998

Surveyor's Michigan License No. 21566

R LCR 7 4R 1Pg U  
JDF

FORM APPROVED BY MICHIGAN BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

