

\$ 4.00 REMONUMENTATION
 \$ 7.00 DEED
 23 DEC 96 12:43 P.M. RECEI A
 RECORDED
 FOREST E. YOUNGLOOD, REGISTER EDS
 WAYNE COUNTY, MI

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

City of Dearborn Heights

For corners in

LIBER 29357 PAGE 426

Wayne Located In: Corner Code #
 (County)

1. Public Land Survey T 2S R 10E D-13
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Compliance with *DPJ*
 ACT 345, P.A. 1990
 APPROVED ON: DEC 17, 1996
 WAYNE COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

I, LAWRENCE R. FEINDT, in a field survey on OCTOBER 23, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

96325770

A. Description of original monument and accessories and/or subsequent restoration:

D-13) South 1/4 Corner of Sections 32, T 2 S, R 10 E

GENERAL LAND OFFICE WAYNE COUNTY BUREAU OF TAXATION
 SET POST FOR CORNER IRON
 POPLAR-12°-N31°W-8 LINKS(5.28') NE'LY-91.49'-EDISON POLE *Found*
 ELM 9°-N72°E-45 LINKS(29.70') SE'LY-34.90°15' MAPLE *Found*
 DECEMBER 16, 1816 WEST-44.50'-N. 1/4 COR. SEC. 5, T3S, R10E
 BY: JOSEPH FLETCHER, DS NW'LY-101.38'-EDISON POLE *Found*

LCRC BY RICHARD W. SWANSON, PS #9748
 RECORDED LI. 19356, PG. 67 DATED MARCH 15, 1976
 WAYNE COUNTY ROAD COMMISSION
 CONCRETE MONUMENT IN BOX
 WNW-132.92'-SPIKE & TAG IN NE SIDE OF EDISON POLE *Found*
 NW-79.25'-X' CUT IN WALK ON NORTH PARALLEL TO VAN BORN *Found*
 NE-76.25'-X' CUT IN WALK ON NORTH PARALLEL TO VAN BORN *Found*
 NE-67.62'-SPIKE & TAG SE SIDE EDISON POLE *Found*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13) South 1/4 Corner of Section 32, T 2 S, R 10 E

Found concrete monument with 1/2" pipe in monument box. Distance to E-13 measured 2645.48' (WPA=2645.36'). Distance to C-13 measured 2626.27' (WPA=2626.25').



NOT A COMMON CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13) South 1/4 Corner of Section 32, T 2 S, R 10 E

Found concrete monument with 1/2" pipe in monument box. Set spike inside pipe and placed Wayne County brass disk stamped with license #21566 on pipe. Road surface is concrete. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N43°E - 67.35' - Found nail and WCRC tag on SE side of utility pole (recorded as 67.62')
 N68°W - 132.84' - Found nail and WCRC tag on SW side of utility pole (recorded as 132.92')
 S48°W - 128.98' - NE corner of house foundation (#25001)
 S80°E - 254.50' - Top center of fire hydrant
 West - 44.52' - Found 1/2" pipe in concrete monument in monument box at north 1/4 corner of Section 5, T 3 S, R 10 E

Signed by Lawrence R. Feindt
 Surveyor's Michigan License No. 21566

Date December 6, 1996