

FEB 28 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1126992 PA 841

For corners in

Wayne  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 2S R 10E E-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 11-20-93 D.P.  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3			⊕									
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Lawrence R. Feindt

I, \_\_\_\_\_, in a field survey on November 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3) Corner Common to Sections 4, 5, 8 & 9, T 2 S, R 10 E

GENERAL LAND OFFICE  
SET POST FOR CORNER

W.O. 16"-S63 W-48 LINKS(31.68')  
MAPLE 12"-S46 E-26 LINKS(17.16')  
DECEMBER 23, 1816  
BY: JOSEPH FLETCHER, DS

WAYNE COUNTY BUREAU OF TAXATION  
IRON  
NE'LY-76.90'-ED. POLE  
SW'LY-60.32'-ED. POLE  
NW'LY-55.96'-ED. POLE

FOUND 1" IRON IN MONUMENT BOX  
S55 E-72.56'-CHISELED "X" ON SW BOLT IN  
CONC. LIGHT BASE  
N45 W-68.08'-TOP CENTER OF FIRE HYDRANT  
N60 E-62.10'-POWER POLE  
WEST -65.92'-RAILROAD SPIKE IN PAVEMENT  
JULY 27, 1982  
BY: MYRON L. PETRIE, PS #19841  
MICHIGAN DEPARTMENT OF TRANSPORTATION  
RECORDED IN LIBER 21484, PAGE 723, WCR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3) Corner Common to Sections 4, 5, 8 & 9, T 2 S, R 10 E

Found 1" solid iron rod in monument box. Distance to D-3 measured 2653.95' (WPA 2653.75'). Corner was confirmed with irons found in "Conley's Warren-Telegraph Subdivision No. 1" as recorded in Liber 52, Page 58, Wayne County records and "Conley's Warren-Telegraph Subdivision" as recorded in Liber 51, Page 71, Wayne County records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3) Corner Common to Sections 4, 5, 8 & 9, T 2 S, R 10 E

Found 1" solid iron rod in monument box at the intersection of Warren Avenue and Telegraph Road, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- Witnesses:
- N54°W - 68.06' - "X" cut in bolt top of fire hydrant
  - N55°E - 62.15' - Found MDOT tag and nail in NW face of utility pole and affixed Wayne County brass disk with PK nail stamped with license #21566 below MDOT tag
  - S56°E - 70.32' - NW bolt of steel light pole #S40DA445
  - S46°W - 44.82' - Set "X" cut in top of curb
  - N81°W - 297.88' - Found WCRC bench mark disk

Signed by Lawrence R. Feindt

Date November 29, 1993

Surveyor's Michigan License No. 21566

RC 1157

93 NOV 30 AM 11:47

2R  
1157