

SURVEY & MONUMENTATION

\$ 7.00 DEED
 8 DEC 95 9:44 A.M. RECEIPT# 68
 FOREST E. WOODS, REGISTER OF DEEDS
 WAYNE COUNTY, MI
 \$ 4.00 REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

City of Dearborn APR 05 1996

For corners in

Wayne
 (County)

COMMISSION

Located In:

Corner Code #/

LIBER 28451 PAGE 028

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-6-95 *DPJ*
 WAYNE COUNTY REMONUMENTATION
 BOARD LOCAL COMMISSIONER

Register of Deeds Stamp & File Number

95262307

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>2S</u> R <u>10E</u> | <u>E-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

Lawrence R. Feindt

I, Lawrence R. Feindt, in a field survey on October 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7 Corner Common to Sections 16, 17, 20 and 21, T 2 S, R 10 E
 GENERAL LAND OFFICE
 SET POST FOR CORNER
 ELM 12"-803 E-13 LINKS(8.58')
 WHITE OAK 9"-828 W-15 LINKS(9.90')
 DECEMBER 22, 1816
 BY: JOSEPH FLETCHER, DS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7) Corner Common to Sections 16, 17, 20 and 21, T 2 S, R 10 E
 No direct evidence of corner was found. Corner was re-established from property irons found in "Dearborn Highlands" as recorded in Liber 40 of Plats, Page 84; "Dearborn-Summit-Drive-Subdivision" as recorded in Liber 41 of Plats, Page 83; and "Hannan's Dearborn Hills Subd'n. No. 1" as recorded in Liber 42 of Plats, Page 2.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7) Corner Common to Sections 16, 17, 20 and 21, T 2 S, R 10 E
 Set railroad spike in center lines of North bound lane of Telegraph Road and Cherry Hill Road. Road surface is concrete with asphalt overlay. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
 Witnesses: N41°E - 53.14' - Set PK nail in NW face of utility pole and affixed Wayne County brass disk stamped with license #21566
 S63°E - 55.49' - Set chiseled "X" in top center of fire hydrant
 S81°W - 145.54' - Set nail & WCR tag in NW face of utility pole
 N31°W - 44.21' - Set chiseled "X" in top back of catch basin
 N45°E - 50.00' - Set T-iron & #21566 cap drilled in concrete walk
 S45°W - 50.00' - Set concrete monument with brass disk stamped with #21566

Signed by Lawrence R. Feindt Date _____
 Surveyor's Michigan License No. 21566

4R
 7D
DPJ