

DEC 22 1998  
 FILE DO NOT MAIL

SURVEY &  
 REMONUMENTATION

MAR 02 1999

Libar-30032

Page-14.0

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

CITY OF DEARBORN  
 For corners in

WAYNE  
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 12-16-98 *DPJ*  
 WAYNE COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, LAWRENCE R. FEINDT, in a field survey on DECEMBER 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	

004557813

12/22/1998

00:32:00

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8 CORNER COMMON TO SECTIONS 20 & 21 T2S-R10E

GENERAL LAND OFFICE

Set 1/4 Sec. post

Beech 16" S20°W 32 Links (21.12')

Beech 6" S89°E 3 Links (1.98')

DEC 23, 1816

By: Joseph Fletcher

\$4.00 REMONUMENTATION  
 \$7.00 DEED

RECORDED  
 FOREST E. YOUNGLOLD, REGISTER OF DEEDS  
 WAYNE COUNTY, MI  
 Receipt #101463

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 CORNER COMMON TO SECTIONS 20 & 21 T2S-R10E

Found no corner or evidence of original corner. Corner was computed by single proration between corners E-7 and E-9. This computed position fell very close to an existing plat corner in "HANNAN'S DEARBORN HILLS SUBD'N NO.1. Therefore the position of the plat corner was held as the position of the quarter corner.

Distance to corner E-7 Measured 2652.98' (GLO = 2640')

Distance to corner E-9 Measured 2653.17' (GLO = 2640')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 CORNER COMMON TO SECTIONS 20 & 21 T2S-R10E

Replaced 1/2" iron pipe with concrete monument and Wayne County brass disk stamped with license #21566 in wooded area. The corner is located East of the right of way of Telegraph Road between Fordson Ave. and Highland Ave.

The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the original corner.

WITNESSES:

8" Ash	N50°E	14.00'	Set nail and WCR tag in SE side
8" Spruce	S12°E	10.75'	Set nail and WCR tag in West side
8" Spruce	S30°W	13.78'	Set nail and WCR tag in North side
6" Spruce	N20°W	21.28'	Set nail and WCR tag in East side

Signed by Lawrence R. Feindt

Date December 16, 1998

Surveyor's Michigan License No. 21566



R LCR 7 4R 1Pg U  
*DPJ*