

SURVEY & MONUMENTATION

\$ 7.00 DEED
 8 DEC 95 9:44 A.M. RECEIPT# 68
 RECEIVED
 FOREST E. VORSTER, REGISTER OF DEEDS
 WAYNE COUNTY, MI

City of Dearborn **APR 15 1996**

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne
 (County)

COMMISSION

Located In:

Corner Code #:

\$ 4.00 REINVESTMENT

LIBER 28451 PAGE 030

Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-6-95 *DRJ*
 WAYNE COUNTY REINVESTMENT
 BOARD OF COMMISSIONERS

Register of Deeds Stamp & File Number

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey | T | <u>2S</u> | R | <u>10E</u> | <u>E-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Lawrence R. Feindt, in a field survey on October 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-11) Corner Common to Sections 28, 29, 32 & 33, T 2 S, R 10 E
 GENERAL LAND OFFICE SET POST FOR CORNER
 BLACK OAK 20"-N61°W-6 LINKS(3.96')
 WHITE OAK 6"-S42°E-27 LINKS(17.82')
 DECEMBER 22, 1818
 BY: JOSEPH FLETCHER, DS
 WAYNE COUNTY BUREAU OF TAXATION CROSS
 NE'LY-46.00'-TELEPHONE POLE
 SW'LY-69.15'-EDISON POLE
 NW'LY-34.40'-MANHOLE COVER

95262309

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-11) Corner Common to Sections 28, 29, 32 & 33, T 2 S, R 10 E
 No direct evidence of corner was found. Corner was re-established from property irons found in "Dearborn Park Subdivision" as recorded in Liber 33, Page 32; and "Dearborn-Telegraph-Subdivision" as recorded in Liber 51, Page 19. Distance to D-11 measured 2629.30' (WPA=2629.58').



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-11) Corner Common to Sections 28, 29, 32 & 33, T 2 S, R 10 E
 Set railroad spike in the center lines of North bound lane of Telegraph Road and Carlisle Avenue. Road surface is concrete with asphalt overlay. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
 Witnesses: N45°E - 56.51' - SW corner of bank building
 S39°E - 40.91' - Set PK nail in top of concrete curb and affixed Wayne County brass disk stamped with license #21566.
 S58°W - 71.92' - Set chiseled "X" in SE corner of traffic signal pole base
 N59°W - 70.68' - Set chiseled "X" in SW corner of traffic signal pole base
 N37°E - 50.00' - Set T-iron & #21566 cap drilled in concrete walk
 S37°W - 50.00' - Set concrete monument with brass disk stamped with #21566

Signed by Lawrence R. Feindt Date _____
 Surveyor's Michigan License No. 21566

4R
7D
DRJ