

FEB 23 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 26992 PA 834

For corners in

Wayne (County)

Located In:

Corner Code -#

- 1. Public Land Survey T 2S R 10E G-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-30-93 DPJ
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Lawrence R. Feindt, in a field survey on October 29, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A circled 'X' is located at the intersection of column G and row 5.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-5) Corner Common to Sections 9, 10, 15 & 16, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER B.O. 10"-N01 W-43 LINKS(28.38') W.O. 12"-S56 W-48 LINKS(31.68') DECEMBER 26, 1816 BY: JOSEPH FLETCHER, DS
WAYNE COUNTY BUREAU OF TAXATION MON. NNE'LY-41.57'-6" PEAR SE'LY -73.30'-ED. POLE SSW'LY-42.76'-5" CEDAR NW'LY -55.84'-ED. POLE
M.D.O.T. (OCT. 23, 1962) MONUMENT BOX AT CORNER OF FORD ROAD AND HAWTHORNE ROADS - TRIANGLE STAMPED IN 4" BRASS DISK IN MON. BOX N10 E-60.11'-MSHD TAG & NAIL IN E. SIDE OF P.P. S45 E-73.31'-MSHD TAG & NAIL IN NE SIDE OF P.P. S45 W-63.15'-MSHD TAG & NAIL IN SE SIDE OF P.P. BY: DONALD C. PYLE, SURVEY CHIEF

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5) Corner Common to Sections 9, 10, 15 & 16, T 2 S, R 10 E

Found brass disk in monument box under asphalt. Corner was confirmed with irons found in "Belmont Park Subdivision" as recorded in Liber 50 of Plats, Page 31, Wayne County records; "Belmont Park Subdivision No. 2" as recorded in Liber 52 of Plats, Page 51, Wayne County records; "Golf View Subdivision No. 1" as recorded in Liber 54 of Plats, Page 82, Wayne County records; and "Dearborn Valley Sub." as recorded in Liber 76 of Plats, Page 65, Wayne County records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5) Corner Common to Sections 9, 10, 15 & 16, T 2 S, R 10 E

Found brass disk under North edge of monument box at the intersection of Ford Road, Hawthorn Road, and Rouge Circle Avenue, and is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N01 W - 62.14' - Found MSHD tag & nail in E. face of utility pole S62 E - 75.37' - Set PK nail in NE face of 7" Maple S46 W - 62.79' - Set PK nail and affixed Wayne County brass disk with license #21566 in SE face of utility pole N65 W - 65.56' - Set "X" in SE bolt of steel light pole #175C7079 face of concrete wall 1.4' above walk S47 E - 31.97' - PK nail in concrete walk 0.5' North of North face of concrete wall

Signed by Lawrence R. Feindt Date November 29, 1993

Surveyor's Michigan License No. 21566

Vertical stamp: FOREST COUNTY REGISTERED LAND SURVEYORS WAYNE COUNTY REGISTERED LAND SURVEYORS