

SURVEY & REMONUMENTATION

RC 1420

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L127792PA277

COMMISSION

For corners in

<u>Wayne</u> (County)	Located In:	Corner Code #
<u>Dearborn Township #09</u>		
1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with ACT 345, P.A. 1990
 APPROVED ON: 12/6/94 DPF
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, Lawrence R. Feindt, in a field survey on October 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11) Corner Common to Sections 27, 28, 33 and 34, T 2 S, R 10 E
 GENERAL LAND OFFICE WAYNE COUNTY BUREAU OF TAXATION
 SET POST FOR CORNER POINT SET IN M.H. COVER
 BLACK ASH 12"-970° E-25 LINKS(16.50') NE'LY-49.25'-TELEPHONE POLE
 BLACK ASH 10"-882° W-17 LINKS(11.22') SE'LY-88.55'-POWER POLE
 DECEMBER 24, 1816 SW'LY-46.85'-POWER POLE
 BY: JOSEPH FLETCHER, DS NW'LY-47.35'-FIRE HYDRANT (SE HOSE CONNECTION)

\$ 15.00 MISCELLANEOUS RECORDING
 21 DEC 94 10:00 AM
 DEPARTMENT OF DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11) Corner Common to Sections 27, 28, 33 and 34, T 2 S, R 10 E
 Manhole and one W.P.A. witness (fire hydrant) were found. No other direct evidence of corner was found. Corner was re-established from property corners found in "Dearborn Boulevard Subdivision" as recorded in Liber 39 of Plats, Page 56; and "Southland Subdivision" as recorded in Liber 41, Page 40. Distance to G-12 measured 2636.46' (WPA = 2637.32').



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11) 1/4 Corner Common to Sections 27, 28, 33 and 34, T 2 S, R 10 E
 Set four chisel marks on manhole rim intersecting at computed corner location at the intersection of Carlisle Avenue and Monroe Road. Road surface is asphalt. Actual corner falls on cover and cannot be set. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
Witnesses: N51°E - 41.54' - Set nail & #21566 cap in NW face of power pole
 S59°E - 44.75' - Set PK nail in North face of power pole and affixed Wayne County brass disk stamped with license #21566
 S53°W - 40.80' - Set nail & #21566 cap in East face of power pole
 N62°W - 47.81' - SE hose connection on fire hydrant (WPA witness)
 N62°W - 48.55' - Set chiseled "X" in top center of fire hydrant

2 R
 11 D - Misc

Signed by Lawrence R. Feindt Date 12/21/94
 Surveyor's Michigan License No. 21566