

RECORDED

FEB 28 1994

COMMISSION

RC 1152

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LI 26992 PA 836

For corners in

Wayne (County) Located In: Corner Code # G-12
1. Public Land Survey T 2S R 10E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with ACT 345, P.A. 1990
APPROVED ON: 11-30-93
WAYNE COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Lawrence R. Feindt, in a field survey on November 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table with 3 columns: GENERAL LAND OFFICE, WAYNE COUNTY BUREAU OF TAXATION, WAYNE COUNTY ROAD COMMISSION. Lists various monuments like IRON, FIRE HYDRANT, GUY POLE, ED. POLE, SE COR. BUILDING with bearings and distances.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12) 1/4 Corner Common to Sections 33 and 34, T 2 S, R 10 E
Found apparent stone in monument box. Distance to G-13 measured 2640.44' (WPA = 2639.98 and shown as 2639.66' on "Pardee's Monroe Blvd. Sub."). Corner was confirmed with irons found in "Pardee's Monroe Blvd. Sub." as recorded in Liber 47 of Plats, Page 56, Wayne County records; "Southland Subdivision" as recorded in Liber 41 of Plats, Page 40, Wayne County records; and "Fordson Manor" as recorded in Liber 41 of Plats, Page 68, Wayne County records.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12) 1/4 Corner Common to Sections 33 and 34, T 2 S, R 10 E
Found apparent stone in monument box at the intersection of Annapolis Avenue and Monroe Road, and is accepted as a careful and faithful reestablishment of the position of the original corner.
Witnesses: N34°E - 45.78' - SW hose connection on fire hydrant (WPA witness)
N34°E - 46.66' - Top bolt on fire hydrant
S59°E - 38.20' - Set "X" cut in rim of gas manhole
S54°W - 41.73' - Set PK nail in SE face of light pole and affixed Wayne County brass disk stamped with license #21566
N70°W - 68.55' - Set PK nail in S'ly face of 18" Oak
N44°E - 31.23' - Center of manhole (WPA witness)
N60°E - 30.64' - Center of manhole (WPA witness)

Signed by Lawrence R. Feindt Date November 29, 1993

Surveyor's Michigan License No. 21566