

**SURVEY &  
MONUMENTATION**

Cities of Detroit  
and Dearborn Heights

APR 15 1996

**LAND CORNER RECORDATION CERTIFICATE**

\$ 7.00 DEED

8 DEC 95 9:45 A.M.

RECEIPT 68

RECOVERED

FOREST E. YOUNG, REGISTER OF DEEDS  
WAYNE COUNTY, MI

For corners in

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

**LIBER 28451 PAGE 032**

\$ 4.00 REMONUMENTATION

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-6-95 *DRJ*

WAYNE COUNTY REMONUMENTATION  
FIELD GROUP COMMITTEE

Register of Deeds Stamp & File Number

Wayne (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>I-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**Lawrence R.  
Feindt**

I, \_\_\_\_\_, in a field survey on October 22, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-4) 1/4 Corner Common to Sections 10 and 11, T 2 S, R 10 E

GENERAL LAND OFFICE	WAYNE COUNTY BUREAU OF TAXATION
SET POST FOR CORNER	IRON
BLACK ASH-NORTH-7 LINKS(4.62')	NE'LY-40.01'-POLE
ELM 10"-N86°W-24 LINKS(15.84')	SE'LY-62.65'-POLE
DECEMBER 19, 1816	SW'LY-37.10'-POLE
BY: JOSEPH FLETCHER, DS	NW'LY-74.40'-POLE

95262311

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4) 1/4 Corner Common to Sections 10 and 11, T 2 S, R 10 E

No direct evidence of corner was found. Corner was re-established from property irons found in "Frischkorn's Estates" as recorded in Liber 42 of Plats, Page 93; "Rouge Park Subdivision" as recorded in Liber 44 of Plats, Page 61; and "Florence Park Subdivision" as recorded in Liber 48 of Plats, Page 82. Distance to I-3 measured 2648.71' (WPA = 2649.20').



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4) 1/4 Corner Common to Sections 10 and 11, T 2 S, R 10 E

Set concrete monument with brass disk in monument box at the intersection of Paul Avenue and Evergreen Road. Road surface is asphalt over concrete. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Witnesses: N50°W - 31.60' - Set nail in SW face of power pole and affixed Wayne County brass disk stamped with license #21566  
 N55°E - 39.94' - Set nail and WCR tag in NW face of power pole (old WPA witness)  
 S37°E - 39.21' - Set nail and WCR tag in NE face of power pole  
 S15°W - 86.65' - Set nail and WCR cap in East face of power pole

Signed by Lawrence R. Feindt Date December 7, 1995  
 Surveyor's Michigan License No. 21566

4R  
70  
*DRJ*