

**SURVEY &  
MONUMENTATION**

\$ 4.00 REMONUMENTATION  
8 DEC 95 9:45 A.M. RECEIPT FOR  
RECORDED  
DORIS E. VIVIAN, REGISTER OF DEEDS  
WAYNE COUNTY, MI

**LAND CORNER RECORDATION CERTIFICATE**

City of Dearborn APR 15 1996

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne COMMISSION Located In:

Corner Code #

\$ 7.00 DEED

**LIBER 28451 PAGE 033**

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-6-95  
WAYNE COUNTY REMONUMENTATION  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- |                                    |   |           |   |            |             |
|------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey              | T | <u>2S</u> | R | <u>10E</u> | <u>I-11</u> |
|                                    | T | _____     | R | _____      | _____       |
|                                    | T | _____     | R | _____      | _____       |
|                                    | T | _____     | R | _____      | _____       |
| 2. Property Controlling in Section | S | _____     | T | _____      | _____       |
|                                    | S | _____     | T | _____      | _____       |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____      | _____       |
|                                    | S | _____     | T | _____      | _____       |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Lawrence R. Feindt, in a field survey on October 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-11) Corner Common to Sections 26, 27, 34 & 35, T 2 S, R 10 E

GENERAL LAND OFFICE SET POST FOR CORNER BLACK ASH 10"-S38°E-11 LINKS(7.26') LYNNWOOD 9"-S82°W-5 LINKS(3.30') DECEMBER 24, 1816 BY: JOSEPH FLETCHER, DS	WAYNE COUNTY BUREAU OF TAXATION MON. SE'LY-94.15'-MANHOLE COVER SW'LY-46.51'-EDISON POLE NW'LY-70.46'-CROSS CUT IN BASE OF CONC. POST
---	---

95262312

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-11) Corner Common to Sections 26, 27, 34 & 35, T 2 S, R 10 E

Found City of Dearborn brass bench mark disk in monument box 0.2'± under asphalt overlay. Corner was confirmed from property irons found in "Ziegler Park Sub." as recorded in Liber 40, Page 97; "Elmhurst Park Sub." as recorded in Liber 41, Page 37; and "Amended Plat of Dearborn Point Sub'n." as recorded in Liber 44, Page 81. Distance to I-12 measured 2666.32' (WPA = 2666.14').



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-11) Corner Common to Sections 26, 27, 34 & 35, T 2 S, R 10 E

Found City of Dearborn brass bench mark disk in monument box at the intersection of Pelham Road, Carlisle Avenue and Outer Drive. Road surface is asphalt over concrete. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

Witnesses: N38°E - 38.07' - Set nail and WCR tag in SE face of power pole  
S78°E -123.70' - Set PK nail in North face of pole and affixed Wayne County brass disk stamped with license #21566  
S36°E - 88.32' - Set nail and WCR tag in East face of power pole  
S44°W - 46.87' - Set nail and WCR tag in South face of power pole

Signed by Lawrence R. Feindt Date \_\_\_\_\_  
Surveyor's Michigan License No. 21566

4R  
7D  
DF