

SURVEY & REMONUMENTATION

APR 25 1995

RC 1422

L127792PA279

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne
(County)
Dearborn Township #09

Located In:

Corner Code #

1. Public Land Survey	T	<u>2S</u>	R	<u>10E</u>	<u>I-13</u>
	T	---	R	---	---
	T	---	R	---	---
	T	---	R	---	---
2. Property Controlling in Section	S	---	T	---	---
	S	---	T	---	---
3. Miscellaneous Property in Sec.	S	---	T	---	---
	S	---	T	---	---

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12/16/94 DBL
WAYNE COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Lawrence R.

I, Feindt, in a field survey on October 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-13) South Corner Common to Sections 34 and 35, T 2 S, R 10 E
GENERAL LAND OFFICE WAYNE COUNTY BUREAU OF TAXATION FOUND 3/8" PIN IN CONC. MON. IN MON. BOX
SET POST FOR CORNER IRON N15°W-39.05'-SE CORNER CB FRAME
BEECH 12"-S43°E-34 LINKS(22.44') NE'LY- 60.40'-IRON N40°E-73.25'-SW CORNER BRICK BUILDING
WHITE OAK 10"-S88°E-28 LINKS(18.48') ENE'LY- 57.75'-TOP FIRE HYDRANT N65°E-97.65'-LIGHT POLE
DECEMBER 16, 1816 SSW'LY- 48.80'-5" ELM S45°E-69.70'-NW CORNER CB FRAME
BY: JOSEPH FLETCHER, DS WEST - 222.02'-MON. BOX MAY 14, 1981
BY: ERVIN P. MILLER, PS #13589
RECORDED LIBER 21160, PAGE 416

FOUND MON IN BOX
NE- 97.64'-WCRC BRASS TAG S. SIDE DE POLE FEBRUARY 7, 1990
SE-137.23'-WCRC TAG W. SIDE DE POLE WITNESSES BY: WAYNE COUNTY OFFICE
SSE-73.17'-"X" CUT IN RIM N. SIDE STORM MH OF PUBLIC SERVICES
NW- 45.48'-"X" CUT IN RIM S. SIDE STORM MH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13) South Corner Common to Sections 34 and 35, T 2 S, R 10 E
Found concrete monument in monument box. Distance to I-12 measured 2611.66' (WPA = 2611.47'). Corner was confirmed with property irons found in "Dearborn Homes Subd'n. # 4" as recorded in Liber 45 of Plats, Page 2; and "Dearborn Homes Subd'n. #5" as recorded in Liber 47 of Plats, Page 43.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13) South Corner Common to Sections 34 and 35, T 2 S, R 10 E
FOUND CONCRETE MONUMENT IN MONUMENT BOX AND PLACED WAYNE COUNTY BRASS DISK STAMPED WITH LICENSE #21566 AT THE INTERSECTION OF ROBINSON ROAD AND VAN BORN ROAD. ROAD SURFACE IS ASPHALT. CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
Witnesses: S06°W - 61.89' - Set "X" cut in East bolt of light pole
N21°W - 39.03' - SE corner of catch basin frame (MDOT witness)
N20°W - 45.28' - Found "X" cut in S'yly side of manhole rim (WCOPS witness)
N36°E - 73.15' - SW corner of brick building (MDOT witness)
N48°E - 66.33' - Top center of fire hydrant
N59°E - 97.63' - Found WCRC tag in South side of DE pole (WCOPS witness)
S66°E - 137.15' - Found WCRC tag in West side of DE pole (WCOPS witness)
West - 220.50±' - Found monument box at I-1 of T3S, R10E (GLO=3.45 ch. [227.70'])

Signed by Lawrence R. Feindt Date 12/21/94
Surveyor's Michigan License No. 21566

2R
11D-MISC