

FEB 28 2000

FILE DO NOT MAIL

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

CITY OF DETROIT  
or corners in

WAYNE  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

Public Land Survey T 2S R 10E J-1

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Liber-30855 Page-7  
99593201 12/29/1999  
F.E. Youngblood, Wayne Co. Register of Deeds  
RDANDSYL

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-9-99 *[Signature]*  
WAYNE COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

LAWRENCE R. FEINDT, in a field survey on December 2, 1999  
to hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
required in the current manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and /or that the corner points  
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of  
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7	8		9		10		11		12		
5												
6	16	17		15		14		13				
7												
8	19	20		21		22		23		24		
9												
10	30	29		28		27		26		25		
11												
12	31	32		33		34		35		36		
13												

A. Description of original monument and accessories and/or subsequent restoration:  
J-1 CORNER COMMON TO SECTION 2 T2S-R10E & SECTION 35 T1S-R10E

GENERAL LAND OFFICE  
Set 1/4 Sec. corner  
B. Ash 9" N47° 30' E 10 Lks (6.60')  
Hickory 6" N61° W 27 Lks (17.82')  
December 16 1816  
By: Joseph Fletcher



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
J-1 CORNER COMMON TO SECTION 2 T2S-R10E & SECTION 35 T1S-R10E

Found a concrete monument in a monument box in the center line of Joy Road and Artesian Avenue.  
Corner was confirmed with irons found in "BONAPARTE PARK SUBDIVISION" as recorded in Liber 49  
Page 99 and "FITZPATRICK'S VILLAS" as recorded in Liber 54 Pg. 23.

Distance to corner K-1 Measured 2631.52' (GLO = 2640.0')  
Distance to corner I-1 Measured 2632.92' (GLO = 2640.0')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
J-1 CORNER COMMON TO SECTION 2 T2S-R10E & SECTION 35 T1S-R10E

Placed a Wayne County Remonumentation disk stamped #21566 over a concrete monument in a  
monument box. The corner is in concrete pavement at the intersection of Joy Road and Artesian  
Avenue. Corner is accepted as a careful and faithful reestablishment of the position of the  
original corner.

WITNESSES:  
N42°E 48.36' Set nail & WCR tag in NW side utility pole  
S52°E 55.54' Found nail & WCR tag in SW side electric pole  
S44°W 48.32' Found nail & WCR tag in NW side utility pole  
N45°W 47.99' Found nail & WCR tag in SW side light pole  
N25°W 101.88' SE corner of brick bldg #19000 (Self Storage)

Signed by Lawrence R. Feindt Date December 9, 1999

Surveyor's Michigan License No. 21566

R LCR 9 4R 10 A [Signature]