

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Wayne COMMISSION Located In:

Corner Code K-4

LIBER 28451 PAGE 034

1. Public Land Survey	T <u>2S</u> R <u>10E</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 4.00 REMONUMENTATION
 Compliance with
 ACT 345, P.A. 1990

APPROVED ON: 12-6-95 *JRF*
 WAYNE COUNTY REMONUMENTATION
 PUBLIC GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Lawrence R. Feindt

I, Lawrence R. Feindt, in a field survey on October 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-4) 1/4 Corner Common to Sections 11 and 12, T 2 S, R 10 E

GENERAL LAND OFFICE
 SET POST FOR CORNER

BEECH 18"-NB1 W-41 LINKS(27.06')
 SUGAR 20"-S25 E-19 LINKS(12.54')
 DECEMBER 19, 1816
 BY: JOSEPH FLETCHER, DS

FOUND CONCRETE MONUMENT IN MONUMENT BOX ON BRIDGE DECK
 N10 W-24.51'-DRILL HOLE IN SQUARE SW CORNER LIGHT POLE
 EAST -10.08'-CHISELED "X" IN STEEL EXPANSION PLATE
 S60 E-49.71'-DRILL HOLE IN SQUARE SW CORNER LIGHT POLE
 MARCH 2, 1964
 BY: BERNARD J. SWIEBODA, SURVEY CHIEF - MDOT

45262313

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4) 1/4 Corner Common to Sections 11 and 12, T 2 S, R 10 E

Found 1/2" iron rod in monument box on bridge deck as documented by the Michigan Department of Transportation in 1964. Distance to K-5 measured 2633.06' (MDOT = 2633.70') Corner was confirmed with irons found in "Frischkorn's Highlands No. 1" as recorded in Liber 41 of Plats, Page 23; "Rycraft Park Subdivision" as recorded in Liber 42 of Plats, Page 25; and "Frischkorn's Southfield Park Sub." as recorded in Liber 70, Page 91.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4) 1/4 Corner Common to Sections 11 and 12, T 2 S, R 10 E

Found 1/2" iron rod in monument box on Paul Avenue bridge deck over M-39. Road surface is concrete with asphalt overlay. Replaced damaged cover and stabilized existing iron with concrete. Corner is accepted as a careful and faithful reestablishment of the position of the original corner.

- Witnesses:
- S62°E - 49.59' - Found drill hole SW corner of light pole (MDOT witness)
 - N21°E - 25.68' - Set PK nail in concrete curb and affixed Wayne County brass disk stamped with license #21566
 - N09°W - 24.56' - Found drill hole SW corner light pole (MDOT witness)
 - N76°W - 128.13' - Set "X" cut in manhole rim
 - S79°W - 121.48' - Found WCRC brass bench mark disk no. 98-09-92 in walk

Signed by Lawrence R. Feindt

Date _____

Surveyor's Michigan License No. 21566