

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

City of Detroit APR 05 1996
For corners in

Wayne COMMISSION
(County)

Located In:

Corner Code ##

LIBER 28451 PAGE 035

Dearborn Township #09

- 1. Public Land Survey T 2S R 10E L-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

\$ 7.00 DEED
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-6-95 [Signature]
WAYNE COUNTY REMONUMENTATION
FIELD GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Lawrence R. Feindt, in a field survey on October 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3) 1/4 Corner Common to Sections 1 and 12, T 2 S, R 10 E
GENERAL LAND OFFICE
SET POST FOR CORNER
BEECH 16"-N60W-11 LINKS (7.26')
ELM 12"-S18 E-5 LINKS (3.30')
DECEMBER 18, 1816
BY: JOSEPH FLETCHER, DS

95262314

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3) 1/4 Corner Common to Sections 1 and 12, T 2 S, R 10 E
No direct evidence of corner was found. Corner was re-established from property irons found in "Hellner Estates" as recorded in Liber 41 of Plats, Page 4; "Morin Park Sub'd'n. No. 1" as recorded in Liber 41 of Plats, Page 94; "West Warren Park Sub." as recorded in Liber 50 of Plats, Page 6; and "Gardner Park Sub. No. 1" as recorded in Liber 54 of Plats, Page 24.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3) 1/4 Corner Common to Sections 1 and 12, T 2 S, R 10 E
Set concrete monument with brass disk in monument box at computed corner location in intersection of Warren Avenue and Asbury Park Avenue. Road surface is concrete with asphalt overlay. The selected location is accepted by the contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.
Witnesses: N78°W -194.74' - Set "X" cut in SE bolt of light pole
N57°W - 98.71' - Set "X" cut in top of steel "I" beam
S42°E - 51.49' - Set "X" cut in NW bolt of light pole
S68°W - 96.87' - Set "X" cut in NE bolt of light pole
South -170.65' - Set PK nail in East face of power pole and affixed Wayne County brass disk stamped with license #21566

Signed by Lawrence R. Feindt Date _____
Surveyor's Michigan License No. 21566